

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
V-21	T15SR27E S26 S25 S35 S36 LS1026 1987	2-38, 39 M.V. 19-1/2°E.	FOUND BASALT STONE 18"x10"x7" FIRMLY SET 8" IN GROUND IN SE EDGE OF 3-1/2 FT. DIAM. STONE MOUND CONSISTING OF APPROX. 12 OTHER LARGE STONES. ORIG. STONE MARKED WITH ONE NOTCH ON SE EDGE AND ONE NOTCH ON NE EDGE. FOUND REMAINS OF ORIG. BT, A 48" DEAD & DOWN WINDFALL PONDEROSA PINE, V.S.-S36T15R28BT ON PITCH FACE SLAB, BEARS S51°E, 39.6 FT. TO APPROX. FACE LOCATION. MONUMENTATION: SET 2-1/2"x30" LONG ALUMINUM PIPE 18" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 10" PONDEROSA PINE, N71-1/4°E, 17.0 FT., SCRIBED-T15SR27ES25BT; 8" JUNIPER, S27-1/4°E, 12.8 FT., SCRIBED-T15SR27ES36BT; 6" JUNIPER, S70-1/4°W, 27.7 FT., SCRIBED-T15SR27ES35BT; 9" PONDEROSA PINE, N13-1/4°W, 29.4 FT., SCRIBED-T15SR27ES26BT. DEPOSITED ORIG. STONE ALONGSIDE CAP AND RAISED STONE MOUND 3 FT. DIAM. TO CAP. SET STEEL POST 5 FT. SOUTH WITH SIGN 54-2 AND SIGN 54-4 FACING CORNER. E-S WIRE FENCE CORNER IS 4 FT. SOUTH AND 7 FT. WEST.
V-23	T15SR27E 1 S25 4 S36 LS1026 1987	2-36, 37 M.V. 19-1/2°E.	FOUND TRIANGULAR SHAPED BASALT STONE 17"x12"x8" LYING FLAT MARKED "1/4" ON BOTTOM FACE. ORIG. STONE ON NORTH SIDE OF VAGUE 3 FT. DIAM. STONE MOUND CONSISTING OF APPROX. 18 OTHER STONES. STONE MOUND VAGUE BECAUSE ENTIRE AREA IS COVERED WITH SURFACE STONE. MONUMENTATION: SET 2-1/2"x30" LONG ALUMINUM PIPE 8" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 10" JUNIPER, N67°E, 73.6 FT., SCRIBED-1/4S25BT; 11" JUNIPER, S8-1/2°E, 119.2 FT., SCRIBED-1/4S36BT. DEPOSITED ORIG. STONE NORTH OF CAP AND RAISED STONE MOUND 3 FT. DIAM. TO CAP. SET STEEL POST 6 FT. WEST WITH SIGN 54-2 AND SIGN 54-4 FACING CORNER. E-W WIRE FENCE IS 32 FT. NORTH.
V-25	T15S R27ER28E S25 S30 S36 S31 LS1026 1987	2-34, 35 M.V. 19-1/2°E.	FOUND BASALT STONE 14"x10"x8" FIRMLY SET 8" IN GROUND IN EAST SIDE OF 2-1/2 FT. DIAM. STONE MOUND CONSISTING OF 6 OTHER STONES. ORIG. STONE MARKED 1 NOTCH SE EDGE 5 NOTCHES NE EDGE AND " " ON TOP. FOUND ORIG. NE BT, A 17" PONDEROSA PINE WITH V.S.-S30T1 BEARS N42°E, 6.3 FT.; FOUND ORIG. SW BT, A 10" PONDEROSA PINE, DEAD & DOWN WITH V.S.-R27 BEARS S66-1/2°W, 19.6 FT.. MONUMENTATION: SET 2-1/2"x30" LONG ALUMINUM PIPE 24" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 25" JUNIPER, S19°E, 56.4 FT., SCRIBED-T15SR28ES31BT; 12" JUNIPER, S49°W, 83.4 FT., SCRIBED-T15SR27ES36BT; 9" JUNIPER, N34-3/4°W, 51.2 FT., SCRIBED-T15SR27ES25BT. DEPOSITED ORIG. STONE NORTH OF CAP AND RAISED STONE MOUND 3 FT. DIAM. TO CAP. SET STEEL POST 5 FT. WEST WITH SIGN 54-2 AND SIGN 54-4 FACING CORNER. S-W WIRE FENCE CORNER IS 1 FT. EAST AND 4 FT. NORTH.
X-21	T15SR27E 1/4 S35 S36 LS1026 1987	2-40, 41 M.V. 19-1/2°E.	FOUND BASALT STONE 12"x6"x5" LYING OVER TO SOUTH MARKED "1/4" ON WEST FACE AND "L" ON TOP IN EAST SIDE STONE MOUND 2-1/2 FT. DIAM. CONSISTING OF APPROX. 10 OTHER SMALL STONES. N-S FENCE IS 3-1/2 FT. WEST. MONUMENTATION: SET 2-1/2"x30" LONG ALUMINUM PIPE 26" IN GROUND WITH 3" ALUMINUM CAP.	BT FOUND: ORIGINAL BT A 45" PONDEROSA PINE BEARS WEST, 84.5 FT., TO FACE. BT MARKED: 9" PONDEROSA PINE, N4-1/2°E, 25.7 FT., SCRIBED-1/4S36BT. DEPOSITED ORIG. STONE NORTH OF CAP AND RAISED STONE MOUND 2 FT. DIAM. TO CAP. SET STEEL POST 5 FT. NORTH OF CAP WITH SIGN 54-2 AND SIGN 54-4 FACING CORNER.
X-25	T15S R27ER28E 1/4 S36 S31 LS1026 1987	2-32, 33 M.V. 19-1/2°E.	SEARCHED FOR NOT FOUND. CORNER LOCATION FELL ON SOUTH SLOPE ABOUT 1 CHAIN NORTH OF E-W RAVINE SOUTH OF ROCKY RIMS. AREA VERY ROCKY WITH MUCH SURFACE STONE. FOUND NO STONE MOUNDS NOR MARKED STONES. RE-ESTABLISH CORNER AT SINGLE PROPORTIONATE POSITION AS DETERMINED BY SURVEY. N-S WIRE FENCE IS 36 FT. WEST. MONUMENTATION: SET 2-1/2"x30" LONG ALUMINUM PIPE 10" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 8" PONDEROSA PINE, N15-1/4°E, 23.7 FT., SCRIBED-1/4S31BT; 14" PONDEROSA PINE, N63°W, 44.0 FT., SCRIBED-1/4S36BT. RAISED STONE MOUND 4 FT. DIAM. TO CAP. SET STEEL POST 5 FT. NORTH WITH SIGN 54-2 AND SIGN 54-4 FACING CORNER.

RECORDATION

OFFICE OF COUNTY SURVEYOR,
COUNTY OF GRANT, STATE OF
OREGON. I HEREBY CERTIFY
THAT THE WITHIN INSTRUMENT
WAS FILED FOR RECORD ON
THE 6 DAY OF Aug,
1987. C.S. NO. 1011.

Robert D. Baggett
COUNTY SURVEYOR

SURVEY OF MALHEUR NATIONAL FOREST BOUNDARY LINES
AROUND SECTION 36, T.15S., R.27E., W.M., AND IN
SECTION 1, T.16S., R.27E., W.M., GRANT COUNTY,
OREGON

SHAKE CADASTRAL SURVEY
CONTRACT NO. 53-04H1-6-0172N
MALHEUR NATIONAL FOREST

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

SHEET 2 OF 5

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong

6/26/87 OREGON
AUGUST 22, 1975
DAVID B. ARMSTRONG
1026

W.O.86-529-C