

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
Z-21	SC T15SR27E <u>S35 ! S36</u> 1976	2-42, 43	FOUND 3-1/4" B.L.M. BRASS CAP MONUMENT ON GALV. IRON PIPE 6" ABOVE GROUND IN N-S FENCE LINE AT WEST SIDE OF ROCK JACK.	BT'S FOUND: (BLM 1976 BEARING TREES) 14" PONDEROSA PINE, N86-1/2°E, 50.8 FT. WITH NEARLY HEALED FACE, V.S.-T15SR27ES36SCBT; 10" PONDEROSA PINE, N29-1/2°W, 61.2 FT., WITH NEARLY HEALED FACE, V.S.-T15SR27ESCBT.
Z-23	SC T15SR27E <u>1/4 S36</u> LS1026 1987	2-44, 45 M.V. 19-1/2°E.	FOUND BASALT STONE 14"X9"X7" LYING IN CENTER OF STONE MOUND 3 FT. DIAM. CONSISTING OF APPROX. 9 OTHER SMALLER STONES. ORIG. STONE MARKED " <u>4s</u> " ON TOP FACE. FOUND 30" JUNIPER, N33-3/4°E, 47.7 FT., WITH NO EVIDENCE OF FACE, ONLY POSSIBLE TREE FOR ORIG. BT. OPENED TREE, FOUND NO EVIDENCE OF FACE OR SCRIBING. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 6" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 8" JUNIPER, N58-1/4°E, 60.6 FT., SCRIBED-1/4S36SCBT; 15" JUNIPER, N18-1/2°W, 62.4 FT., SCRIBED-1/4S36SCBT. DEPOSITED ORIG. STONE NORTH OF PIPE AND RAISED STONE MOUND 4 FT. DIAM. TO CAP. SET STEEL POST 5 FT. EAST WITH SIGN 54-2 AND SIGN 54-4 FACING CORNER. E-W FENCE IS 2-1/2 FT. NORTH.
Z-25	SC T15S R27ER28E <u>S36 ! S31</u> LS1026 1987	2-30, 31 M.V. 19-1/2°E.	CORNER LOCATION FELL NEAR N-W ROCK JACK FENCE LOCATION ON GENTLE SOUTH SLOPE. NO TRACE WAS FOUND OF ORIG. POST NOR PITS. NO TRACE OF ORIG. BT WAS FOUND. RE-ESTABLISHED CORNER AT SINGLE PROPORTIONATE POSITION AS DETERMINED BY SURVEY. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 19" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 7" JUNIPER, N84-1/2°E, 62.9 FT., SCRIBED-T15SR28ES31SCBT; 15" PONDEROSA PINE, N20-1/2°W, 44.5 FT., SCRIBED-T15SR27ES36SCBT. RAISED STONE MOUND 3 FT. DIAM. TO CAP. SET STEEL POST 5 FT. NORTH WITH SIGN 54-2 AND SIGN 54-4 FACING CORNER. N-W WIRE FENCE CORNER IS 7 FT. WEST AND 4 FT. NORTH.
Z-2/3	T15SR28E LINE TREE S31	2-47, 49 M.V. 19-1/2°E.	FOUND A 41" PONDEROSA PINE WITH LINE BLAZE 12" LONG WITH 2 HACK MARKS ON BOTH EAST AND WEST SIDES OF TREE. THE ORIG. SIZE CALL OF 18" IS A MISTAKE AS THIS TREE WAS APPROX. 36" WHEN MARKED. TOP IS BROKEN OUT OF TREE APPROX. 30 FT. ABOVE GROUND. I ACCEPT AS THE ORIGINAL LINE TREE AND USE TO DEFINE LINE ALONG STANDARD PARALLEL.	PAINTED RED BAND AROUND LINE TREE AND NAILED "ATTENTION-SIGN 54-4" SIGNS ON NORTH & SOUTH SIDES OF TREE. BT'S MARKED: 17" PONDEROSA PINE, N10-1/4°E, 99.3 FT., SCRIBED-AP S31 BT; 5" JUNIPER, N59°W, 37.8 FT., SCRIBED-"X" AT DBH "BT". SET STEEL POST 5 FT. WEST WITH SIGN 54-4 FACING LINE TREE.
Z-3	SC T15SR28E <u>1/4 S31</u> LS1026 1987	2-57, 58 M.V. 19-1/2°E.	FOUND STONE 15"X12"X6" BROKEN INTO TWO PIECES LYING FLAT IN 3" DEEP EARTH CAST. EXAMINED STONE CAREFULLY BUT COULD FIND NO DEFINITE MARKS. THERE ARE NO OTHER STONES AT ALL IN THE VICINITY AND THE SURVEY INTO THE SECTION COR. TO EAST CONFIRMS THE PROPORTIONATE POSITION WOULD BE WITHIN A FEW (1-2) FEET OF THE STONE. ACCEPT AS ORIGINAL CORNER. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 10" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 9" JUNIPER, N72-1/4°E, 46.4 FT., SCRIBED-1/4S31SCBT; 15" JUNIPER, N25-1/4°W, 76.7 FT., SCRIBED-1/4S31SCBT. DEPOSITED ORIGINAL STONE NORTH OF PIPE AND RAISED STONE AND EARTH MOUND 4 FT. DIAM. TO CAP. SET STEEL POST 5 FT. EAST WITH SIGN 54-4 FACING CORNER.
Z-5	SC T15SR28E <u>S31 ! S32</u> LS1026 1987	2-55, 56 M.V. 19-1/2°E.	FOUND NO EVIDENCE OF ORIG. POST. FOUND ORIG. NW BT, A 34" PONDEROSA PINE, N29-1/2°W, 54.8 FT. TO CHAINING NOTCH, 56.2 FT. TO CENTER, V.S.-S31T15R28BT ON OPEN FACE. FOUND ORIG. NE BT, A 22" PONDEROSA PINE, N36-1/4°E, 26.4 FT. TO ORIG. FACE, 26.7 FT. TO CENTER WITH HEALED SCAR FACE. RE-SET COR. AT RECORD DIST. INTERSECTION FROM CHAINING NOTCHES ON ORIGINAL BT'S. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 20" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT MARKED: 10" PONDEROSA PINE, N77-1/2°W, 32.3 FT., SCRIBED-T15SR28ES31SCBT. RAISED EARTH MOUND TO CAP, NO STONE AVAILABLE. SET STEEL POST 5 FT. EAST WITH SIGN 54-4 FACING CORNER.

# RECORDATION

OFFICE OF COUNTY SURVEYOR,  
COUNTY OF GRANT, STATE OF  
OREGON. I HEREBY CERTIFY  
THAT THE WITHIN INSTRUMENT  
WAS FILED FOR RECORD ON  
THE 6 DAY OF Aug,  
1987. C.S. NO. 1011.

*Robert D. Ingram*  
COUNTY SURVEYOR

SURVEY OF MALHEUR NATIONAL FOREST BOUNDARY LINES  
AROUND SECTION 36, T.15S., R.27E., W.M., AND IN  
SECTION 1, T.16S., R.27E., W.M., GRANT COUNTY,  
OREGON

SHAKE CADASTRAL SURVEY  
CONTRACT NO. 53-04H1-6-0172N  
MALHEUR NATIONAL FOREST

ARMSTRONG SURVEYING & ENGINEERING, INC.  
378 EAST SECOND STREET  
PRINEVILLE, OREGON 97754  
503/447-7791

SHEET 3 OF 5

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David B. Armstrong*  
6/26/87 OREGON  
AUGUST 22, 1973  
DAVID B. ARMSTRONG  
1026

W.O.86-529-C