

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
A-21	T15SR27E S35 S2   S1 T16SR27E CC	2-50, 51 M.V. 19-1/2°E.	FOUND 40d NAIL & LATHE FROM C.S. 897 AT PROPORTIONAL DISTANCES FROM THE ORIG. BT'S. EXCAVATING AT THIS POINT FOUND REMAINS OF ROTTED WOOD HUB & BURIED & BROKEN GLASS BOTTLE ALONGSIDE NAIL PRESUMABLY FROM B.L.M. 1975 SURVEY. FOUND ORIG. NE BT, A 59" PONDEROSA PINE SAWED STUMP WITH V.S.-"CC" CHAINING NOTCH "BT"-LOG TO MILL, N11°E, 32.4 FT. TO CHAINING NOTCH; ORIG. SW BT, A 63" PONDEROSA PINE SAWED STUMP WITH V.S.-"R27ES2" CHAINING NOTCH "BT", LOG TO MILL, S7°W, 110.1 FT., TO CHAINING NOTCH. I ACCEPT THE NAIL POSITION AND REMONUMENT. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 24" IN GROUND WITH 3" ALUMINUM CAP.	BT'S MARKED: 14" PONDEROSA PINE, S16°E, 32.6 FT., SCRIBED-T16SR27ES1CCBT; 17" PONDEROSA PINE, S51°W, 49.9 FT., SCRIBED-T16SR27ES2CCBT. RAISED STONE MOUND 2-1/2 FT. DIAM. TO CAP. SET STEEL POST 5 FT. SOUTH WITH SIGN 54-4 FACING CORNER. E-W WIRE FENCE IS APPROX. 70 FT. NORTH.
A-23	T15SR27E 1/4 S1 T16SR27E LS1026 1987	2-4, 5 M.V. 19-1/2°E.	NONE. CORNER NOT PREVIOUSLY ESTABLISHED. E-W WIRE FENCE IS 6 FT. SOUTH. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 12" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 12"X16" DOUBLE JUNIPER, S20°W, 248.5 FT., SCRIBED-1/4S1BT; 19" PONDEROSA PINE, S82-1/4°W, 166.6 FT., SCRIBED-1/4S1BT. RAISED STONE MOUND 3 FT. DIAM. TO CAP. SET STEEL POST 5 FT. WEST WITH SIGN 54-2 AND 54-9 FACING CORNER.
A-25	T15SR27E S36 S1   S6 R27ER28E T16S CC LS1026 1987	2-27, 28 M.V. 19-1/2°E.	FOUND ORIG. SW BT, A 39" PONDEROSA PINE WITH PARTIALLY HEALED FACE WITH V.S.-16R28, S41°W, 127.7 FT. FROM CAP. FOUND REMAINS OF ORIG. SE BT, A 48" DEAD & DOWN BUCKSKIN PONDEROSA PINE WITH V.S.-S6T16SR28BT, S58-1/2°E, 84.2 FT. FROM CAP. FOUND NO TRACE OF ORIG. POST. TRUE CC POSITION AS MONUMENTED IS S0°06' 50"W, 1.78 FT. FROM POSITION AS DETERMINED FROM BT'S. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 12" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT MARKED: 10" PONDEROSA PINE, S51°E, 94.2 FT., SCRIBED-T16SR28ES6CCBT. RAISED STONE MOUND 4 FT. DIAM. TO CAP. SET STEEL POST 5 FT. EAST WITH SIGN 54-2 AND SIGN 54-4 FACING CORNER. E-W FENCE IS 3 FT. NORTH.
C-21	T16SR27E 1/4 S2   S1 1985 OPLS 598	1-29 M.V. 19-1/2°E.	FOUND 3-1/4" ALUMINUM CAP MONUMENT ON 2-1/2" O.D. ALUMINUM PIPE 12" ABOVE GROUND IN CENTER OF STONE MOUND.	BT'S FOUND: 17" JUNIPER, N84°E, 65.7 FT., WITH V.S.-1/4S1BT; 12" JUNIPER, N33°W, 44.5 FT., WITH V.S.-1/4S2BT.
C-25	T16S R27ER28E 1/4 S1   S6 LS1026 1987	2-25, 26 M.V. 19-1/2°E.	FOUND SANDSTONE 14"X10"X9" LYING LOOSE ALONGSIDE REMNANTS OF STONE MOUND 2 FT. DIAM. CONSISTING OF 4 OTHER STONES, ORIG. STONE FAINTLY MARKED "4" ON DOWN FACE. FOUND REMAINS OF THE ORIG. BT, A 40" DEAD & DOWN PONDEROSA PINE SNAG, BADLY ROTTEN, WITH V.S.-1/4SBT, ON PITCH FACE, N15°W, 18.5 FT. TO STUMP HOLE FROM CENTER OF STONE MOUND. ACCEPT CENTER STONE MOUND AS CORNER. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 18" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 8" PONDEROSA PINE, N24-3/4°E, 46.2 FT., SCRIBED-1/4S6BT; 10"X10" DOUBLE PONDEROSA PINE, N75-3/4°W, 43.9 FT., SCRIBED-1/4S1BT. DEPOSITED ORIGINAL STONE NORTH OF PIPE AND RAISED STONE AND EARTH MOUND 3 FT. DIAM. TO CAP. SET STEEL POST 5 FT. NORTH WITH SIGN 54-4 FACING CORNER.

RECORDATION  
OFFICE OF COUNTY SURVEYOR,  
COUNTY OF GRANT, STATE OF  
OREGON. I HEREBY CERTIFY  
THAT THE WITHIN INSTRUMENT  
WAS FILED FOR RECORD ON  
THE 6 DAY OF Aug,  
1987. C.S. NO. 1011.

*Robert D. Lagon*  
COUNTY SURVEYOR

SURVEY OF MALHEUR NATIONAL FOREST BOUNDARY LINES  
AROUND SECTION 36, T.15S., R.27E., W.M., AND IN  
SECTION 1, T.16S., R.27E., W.M., GRANT COUNTY,  
OREGON  
SHAKE CADASTRAL SURVEY  
CONTRACT NO. 53-04H1-6-0172N  
MALHEUR NATIONAL FOREST

ARMSTRONG SURVEYING & ENGINEERING, INC.  
378 EAST SECOND STREET  
PRINEVILLE, OREGON 97754  
503/447-7791

SHEET 4 OF 5

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David B. Armstrong*  
6/26/87 OREGON  
AUGUST 22, 1975  
DAVID B. ARMSTRONG  
1026

W.O.86-529-C