

COR. NO.	CAP MARKINGS	FIELD BOOK-PAGE/DECL.	EVIDENCE FOUND	CORNER ACCESSORIES
D-21	T16SR27E S1/16 S2 S1 1985 OPLS 598	1-28 M.V. 19-1/2°E.	FOUND 3-1/4" ALUMINUM CAP MONUMENT ON 2-1/2" O.D. ALUMINUM PIPE FLUSH WITH GROUND WITH STONE MOUND AROUND CAP.	BT'S FOUND: 18" JUNIPER, N44°E, 54.1 FT., WITH V.S.-S1/16S1BT; 16" JUNIPER, N43°W, 176.3 FT., WITH V.S.-S1/16S2BT. SET ADDITIONAL STEEL POST 5 FT. EAST WITH SIGN 54-2 ATTACHED.
D-23	T16SR27E C S1/16 S1 C LS1026 1987	2-54 M.V. 19-1/2°E.	NONE. CORNER NOT PREVIOUSLY ESTABLISHED. MONUMENTATION: SET 2-1/2"X30" LONG ALUMINUM PIPE 6" IN GROUND TO BEDROCK WITH 3" ALUMINUM CAP.	BT'S MARKED: 9" PONDEROSA PINE, N68-1/4°E, 7.8 FT., SCRIBED-CS1/16S1BT; 8" JUNIPER, S0-1/4°W, 31.5 FT., SCRIBED-CS1/16S1BT. RAISED STONE MOUND 3-1/2 FT. DIAM. TO CAP. SET STEEL POST 5 FT. SOUTH WITH SIGN 54-2 AND SIGN 54-9 FACING CORNER.
E-23	T16SR27E 1/4 S1 S12 1985 OPLS 598	1-22 M.V. 19-1/2°E.	FOUND 3-1/4" ALUMINUM CAP MONUMENT ON 2-1/2" O.D. ALUMINUM PIPE 3" ABOVE GROUND IN CENTER OF MOUND OF STONE.	BT'S FOUND: 9" PONDEROSA PINE, N34°E, 10.7 FT., WITH V.S.-1/4S1BT; 7" PONDEROSA PINE, S46°E, 11.7 FT., WITH V.S.-1/4S12BT. SET ADDITIONAL STEEL POST 5 FT. NORTH OF CORNER WITH SIGN 54-2 ATTACHED.

CORNER NOTES

BOOK AND PAGE NUMBERS REFER TO FIELD BOOK AND PAGE. ALL CORNER MONUMENTS SET ARE 2-1/2 INCH O.D. ALUMINUM PIPE 30 INCHES LONG WITH 3 INCH ALUMINUM CAP (UNLESS DIFFERENT MONUMENT IS SPECIFIED) MARKED AS PER CORNER DIAGRAM. ALL BEARING TREES ARE SCRIBED AS PER B.L.M. MANUAL OF INSTRUCTIONS, 1973, WITH THE ADDITION OF A BRASS WASHER STAMPED "AS&E LS1026" NAILED IN LOWER PORTION OF BLAZE. BEARINGS TO BEARING TREES ARE BY STAFF COMPASS USING DECLINATION AS NOTED, DISTANCES ARE MEASURED TO CENTER SIDE OF BEARING TREE. SEE ALSO ACCOMPANYING CERTIFIED RECORD OF LAND CORNER MONUMENTATION FOR ALL SECTION AND 1/4 CORNERS SET. THIS CORNER RECORD SHOULD BE CONSULTED FOR A MORE COMPLETE DESCRIPTION OF EVIDENCE FOUND AND MONUMENTATION OF CORNER. PAINTED RED BAND AND FACES RED AND NAILED SIGNS 54-3 AND 54-9 OR 54-4 TO ALL BEARING TREES.

RECORDATION

OFFICE OF COUNTY SURVEYOR,
COUNTY OF GRANT, STATE OF
OREGON. I HEREBY CERTIFY
THAT THE WITHIN INSTRUMENT
WAS FILED FOR RECORD ON
THE 6 DAY OF Aug,
1987. C.S. NO. 1011.

Robert D. Sayre
COUNTY SURVEYOR

SURVEY OF MALHEUR NATIONAL FOREST BOUNDARY LINES
AROUND SECTION 36, T.15S., R.27E., W.M., AND IN
SECTION 1, T.16S., R.27E., W.M., GRANT COUNTY,
OREGON

SHAKE CADASTRAL SURVEY
CONTRACT NO. 53-04H1-6-0172N
MALHEUR NATIONAL FOREST

ARMSTRONG SURVEYING & ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
503/447-7791

SHEET 5 OF 5

REGISTERED
PROFESSIONAL
LAND SURVEYOR

David B. Armstrong

6/26/87 OREGON
AUGUST 22, 1973
DAVID B. ARMSTRONG
1026

W.O.86-529-C