

LEGEND

◆	- MONUMENT FOUND , TYPE AND SIZE AS STATED
<◇>	- MONUMENT SET , TYPE AND SIZE AS STATED
P/C	- 2 1/2 "x30" ALUMINUM PIPE WITH 3" ALUMINUM CAP
{ }	- ORIGINAL G.L.O. RECORD BEARINGS AND DISTANCE AS SURVEYED BY BAIRD FORB. IN 1890 UNDER CONTRACT #360
[]	- ORIGINAL G.L.O. RECORD BEARING AND DISTANCE AS SURVEYED BY HENRY N. COOKE IN 1882 UNDER

- RANGE LINE - SURVEYED BY BANFORD 1086 IN 1880 UNDER CONTRACT #344
- - DEPENDENT RESERVE BY HENRY W. COOKE IN 1882 UNDER CONTRACT #427
- SUBDIVISION - HENRY W. COOKE, 1882, CONTRACT #427
- OTHER - DEPENDENT RESERVE OF W1/2 NORTH LINE OF SECTION 1 BY D.L.M. IN 1916

THIS IS A DEPENDENT RETRACTIONMENT SURVEY OF SECTIONS 1 AND 12, T19S, R27E, AND PORTIONS OF THE RANGE LINE BETWEEN RANGES 27 AND 28 EAST TO MONUMENT AND DEFINE NATIONAL FOREST BOUNDARIES, AS SHOWN. NO EVIDENCE WAS FOUND OF THE EX-1, 1 $\frac{1}{2}$, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, OR 13 $\frac{1}{2}$. THESE CORNERS WERE ESTABLISHED AT SINGLE-PROPORTIONATE MEASURES PER HENRY COOK'S SURVEY IN 1882. CORNERS WERE ESTABLISHED ON THE RANGE LINE WERE SET ON LINE BETWEEN THE SENIOR CORNERS AS SET BY RANDOLF FORBES IN 1880. THE CORNER $\frac{10}{16}$ IS A JUNIOR CORNER AND THE AMENDED POSITION WAS NOT MONUMENTED. ALL NEW CORNERS AND ACCESSORIES ARE MARKED IN ACCORDANCE WITH THE "MANUAL OF INSTRUCTIONS FOR THE SURVEY OF THE PUBLIC LANDS OF THE UNITED STATES." NEW BEARING TREES HAVE USGS TAGS 5A-3, PLUS USFS TAGS 5A-4 OR 5A-7, AND A RED PANT BAND. BEARING TREE DISTANCES WERE MEASURED TO A LOD NAIL DRIVEN INTO THE BASE OF THE TREE AT SIDE-CENTER AFFIXED WITH A 11 $\frac{1}{2}$ " ALUMINUM WASHER MARKED C.WAYNE COOK - PLUS 107818. BASIS OF MERIDIAN SOLAR-ORIENTED TO OBSERVATION TAKEN AT 1/4 $\frac{11}{16}$, T.19S, R.27E.

TRaverse, sCLAR-ORIENTED
EQUIPMENT: ZEISS TH-M3 THEODOLITE, CITATION EDM,
HEWLETT- PACKARD 3800A EDM, LUKFIM 300'-TAPE
FIELD CREW: C. WAYNE COOK, LAUREN R. EDGAR, STEVE
J. EVERETT, A. D. COOK, C. G. COOK

C. WAYNE COOK
3180 ALDERCREST ROAD
HILLAMOOK, OREGON 97141

OREGON
JULY 22, 1977
C. WAYNE COOK
1098

RECEIVED AND
FILED

OCT 12 1987
OFFICE OF COUNTY SURVEY
Robert R. Brown
Attest: Michael C. Brown

1

