

ASA  
SMITH

MCHALEY'S  
ADDITION

RECEIVED AND  
FILED

APR 13 1988

OFFICE OF COUNTY SURVEYOR  
Attest: *Robert D. Bagett*

**NARRATIVE:**

This survey was performed at the request of Pat O'Hara. The purpose of this survey was to locate a dividing line through the Tim Lillebo tract as Mr. O'Hara is purchasing the portion of land lying west of said dividing line.

A search was made of the available records pertaining to this survey. Field measurements were made to locate existing monuments and fence lines in the area. New monuments were set on the dividing line as shown hereon.

In the interest of economy, Mr. O'Hara did not authorize the determination and location of the other boundaries of this tract. A subdivisional breakdown of section 2 will be required for the north boundaries of this tract. No monumentation of record exists along the south side of the Reservoir Lot or along the north line of Mchaley's Addition. The portion of Harris Ave. North is shown on the Plat of Amended Reservoir Addition, but no width is shown, it scales about 40 feet in width.

Point being 1428.67 feet North  
& 2786.68 feet East of the  
SW corner of section 2, T13S,  
R33 E, W.M.

Property line not determined  
in this survey.

Property line not determined  
in this survey.

Property line not determined in this survey.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. Bagett*

OREGON  
JULY 12, 1963  
ROBERT D. BAGETT  
598



**BASIS OF BEARINGS**  
SOLAR OBSERVATION

**LEGEND**


○ Set 5/8" x 30" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER

● Found 5/8" iron pin of record with attached yellow cap.

x — x Fence line

**REFERENCES**

Record Plat of MCHALEY'S ADDITION  
Record Plat of AMENDED RESERVOIR ADD.  
Deed Records Book 129 Page 563  
Record Map of Survey No. 675

 <b>BAGETT - GRIFFITH &amp; ASSOCIATES</b> John Day, Oregon		
Map of Survey OF A LINE SITUATED IN THE W $\frac{1}{2}$ SE $\frac{1}{4}$ OF SECTION 2, T13S, R33E, W.M. GRANT COUNTY, OREGON		
SURVEYED FOR	PAT O'HARA	
SURVEYED BY	R.D.B. & J.L.W.	3/23/88
Scale: 1" = 50'	Drawn by: J.L.W.	3/24/88