




BASIS OF BEARINGS
 SOLAR OBSERVATION

- LEGEND**
- ⊙ Set 1/2"x30" galvanized iron pipe with attached Grant County Surveyor Brass Cap.
 - Set 5/8"x30" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER.
 - () Record GLO bearing & distance

REFERENCES

Original GLO Field Notes
 Deed Records Book 132 Page 1-2

NARRATIVE:
 This survey was performed at the request of Lanny Westbrook. The purpose of this survey was to locate the appropriate section and 1/4 section corners of sections 5 and 6 as shown and to set the 5/16 corner between sections 5 & 6 and the 1/16 corner between sections 5 & 8. A search was made of the available records pertaining to this survey. Field measurements were made to locate existing monuments. New monuments were set in accordance with the evidence found. During the course of this survey I remonumented 5 government corners from recovered existing original corner evidence. We searched for corners along the north and west boundary of section 6 and for the north 1/4 corner of section 5, but found no conclusive evidence of these corners.

NOTE: For a detailed explanation of corner evidence found new corners set, and bearing tree information, see corner restoration sheets filed in the Corner Restoration Book.

RECEIVED AND
 FILED
 APR 13 1988
 OFFICE OF COUNTY SURVEYOR
 GRANT COUNTY, OREGON

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

 OREGON
 JULY 12, 1983
 ROBERT D. BAGETT
 598

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon			
Map of Survey DEPENDENT RESURVEY OF SELECTED LINES IN SECTIONS 5 & 6 T7S, R29E, W.M. GRANT COUNTY, OREGON			
SURVEYED FOR	James L. Westbrook		
SURVEYED BY	R.D.B. & J.L.W. & D.B.	3/14/88	
Scale: 1"= 1000'	Drawn by: J.L.W.	3/25/88	