



BASIS OF BEARINGS
SOLAR OBSERVATION

- LEGEND**
- Found 5/8" iron pin of record
 - Set 5/8" x 30" iron pin with attached yellow plastic cap marked B-G-A SURVEY MARKER
 - Tract number as shown on West Bench Land Partition, Survey No. 324.
 - Offset distance from centerline of road to found iron pin.

REFERENCES

Record Map of Survey No's 324, 334, 528, 646, 762

Deed Record Book 110 Page 900-905

NARRATIVE: This survey was performed at the request of Marshall Gilmore, Attorney, acting in behalf of the Grant County Court. The purpose of this survey was to locate Road Easement 'H' and a portion of Road Easement 'G', West Bench Land Partition, and to mark the angle points, P.C.'s and P.T.'s of the curves 30 feet each side of centerline as shown hereon.

A search was made of the available records pertaining to this survey. Field measurements were made to locate existing monuments. New monuments were set in accordance with the evidence found and at record as shown hereon.

It is the intent of the land owners along Road Easement 'H' and the portion of Road Easement 'G' shown hereon, to grant to the county, for road purposes an easement 60 feet in width, 30 feet on each side of the centerline of Road easement 'H' and the portion of Road Easement 'G' shown hereon. When the county accepts these easements the designation for Road Easement 'H' will be County Road No. 74-H; the designation for that portion of Road Easement 'G' shown hereon will be County Road No. 74-G. It was decided by the roadmaster to end proposed County Road No. 74-G at engineers centerline station 56+75.88 PT as shown hereon.

RECEIVED AND
FILED
JUL 12 1988
J. L. W.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
ROBERT D. BAGGETT
598

BAGGETT, GRIFFITH & ASSOCIATES John Day, Oregon			
MAP OF SURVEY PROPOSED COUNTY ROAD NO. 74-G & 74-H SITUATED IN THE NE 1/4, SE 1/4, E 1/2 SW 1/4, SE 1/4 NW 1/4 OF SEC. 33 ALSO IN THE NW 1/4 NW 1/4 OF SEC. 34, T13S, R31E, W.M. GRANT COUNTY, OREGON			
SURVEYED FOR	GRANT COUNTY ROAD DEPARTMENT		
SURVEYED BY	R.D.B. & J.L.W. & K.J.W.	July, 1988	
Scale: 1"=200'	Drawn by: J.L.W.	8/11/88	