



NARRATIVE: This survey was performed at the request of Marshall Gilmore, attorney, acting in behalf of the Grant County Court. The purpose of this survey was to locate Road Easement 'D' and Road Easement 'D' Extended, Westbench Land Partition, also to locate the existing road where it deviates from Road Easement 'D' as described, also to mark the right of way as shown hereon. The adjoining landowners intend to grant to the county, for road purposes, the easement as shown hereon.

A search was made of the available records pertaining to this survey. Field measurements were made to locate existing monuments and the existing centerline of Road Easement 'D' and Road Easement 'D' Extended. New monuments were set in accordance with the evidence found and at locations approved by Marshall Gilmore, as shown hereon. The existing road generally stays within the easements as described in Deeds Book 110, Page 903 and Book 128, Page 314, except between stations 11+35.95 to 14+62.15 and 19+15.00 to 21+65.00 where an additional 15 feet is needed to contain the cutbank and fill slope of the existing road as shown. From centerline station 27+91.73 to the terminal end of this easement, at station 44+30.52 the existing road deviates from the described centerline. We were instructed to follow the existing road centerline and mark the sidelines, 30 feet on each side of centerline of this proposed new alignment.

**BASIS OF BEARINGS**  
SOLAR OBSERVATION

**LEGEND**

- Found 5/8" iron pin of record
- Set 5/8" x 30" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER.
- ① Tract number, West Bench Land Partition

**REFERENCES**

Deed Records Book	110	Page 903
	119	115
	119	738
	120	985
	123	309
	124	180
	125	994
	128	314
	130	493-494
	133	436-438
	134	136-137

Record Map of Survey No's 324, 548, 572, 762

RECEIVED AND  
FILED

DEC 2 1 1988

GRANT COUNTY CLERK

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Robert D. Bagett  
OREGON  
JULY 12, 1983  
ROBERT D. BAGETT  
598

**BAGETT - GRIFFITH & ASSOC.**

John Day, Oregon

MAP OF SURVEY  
PROPOSED COUNTY ROAD NO. 74-D  
SITUATED IN THE SW 1/4 NE 1/4; NW 1/4 SE 1/4; NE 1/4 SW 1/4;  
SE 1/4 NW 1/4; SECTION 28, T13S, R31E, W.M.

GRANT COUNTY OREGON

SURVEYED FOR GRANT COUNTY ROAD DEPARTMENT

SURVEYED BY R.D.B. & J.L.W. 11-9-88

Scale 1"=100' Drawn By J.L.W. 11-10-88

RECORD MAP OF SURVEY NO. 1055