



NARRATIVE: This survey was performed at the request of Gayle Ingle, Mayor of the Town of Monument. The purpose of this survey was to locate the tract of land encompassing the existing landfill site for the Town of Monument. Jack Cavender, landowner, Gayle Ingle, and myself met at the proposed site. Mr. Cavender and Mr. Ingle agreed on the location of the proposed site in section 36. I was instructed to determine approximately where the east line of section 36 is in relation to the landfill site. Upon doing so it turns out that this section line runs through the open trench of the landfill. Mr. Cavender said he would have to get the area lying east of the section line released, as he was buying it under contract.

After a period of time I contacted Jack Cavender and Jim Stubblefield, councilman. At that time I was instructed to complete the survey as shown hereon. A search was made of the available records pertaining to this survey. Field measurements were made to locate the E 1/4 corner of section 36, which I had found and remonumented in 1973. New monuments were set at locations approved by Mr. Cavender. I did not fully research the status of the road shown on the westerly portion of this tract. According to Mr. Cavender this road was the county road that went up on top, prior to the relocation of the Top County Road No. 3. To Mr. Cavender's knowledge this old road has not been abandoned.

BASIS OF BEARINGS SOLAR OBSERVATION

LEGEND

- Found Grant County Surveyor Brass Cap.
- Set 5/8" x 30" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER.
- x—x Fence line

REFERENCES

Deed Record Book 92 Page 452
118 82

RECEIVED AND
FILED

SEP 18 1988

OFFICE OF COUNTY SURVEYOR
Robert D. Bagett

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1983
ROBERT D. BAGETT
598

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon			
MAP OF SURVEY OF A TRACT OF LAND SITUATED IN THE SE 1/4 NE 1/4 OF SEC. 36, T8S, R27E, AND GOV'T LOT 4 OF SEC. 31 T8S, R28E, W.M.			
GRANT COUNTY, OREGON			
SURVEYED FOR	TOWN OF MONUMENT		
SURVEYED BY	R.D.B. & J.L.W.	4/27/89 and 8/2/89	
Scale: 1" = 50'	Drawn by: J.L.W.		

RECORD MAP OF SURVEY NO. 1080