

CORNER RECORDS:

ALL CORNER ARE MONUMENTED WITH A 2 1/2" x 30" LONG ALUM. MON. STAMPED AS SHOWN, ORIGINAL G.L.O. STONE CORNERS ARE BUIED ALONGSIDE THE ALUM. MONUMENT AND A STEEL FENCE POST WITH A 54-9 SIGN, "SURVEY MONUMENT" ALONGSIDE THE CORNER.

ALL REFERENCE MONUMENTS ARE BEARING TREES-HAVE A 6" BAND OF RED PAINT, 54-3 SIGN "BEARING TREE", 54-9 SIGN, "SURVEY MONUMENT" AND A BRASS WASHER STAMPED PLS. 1288.

T. 188 R 31 E
1/4 S 32
PLS 1288
1989

FOUND 14" x 12" x 7" MARKED STONE. FOUND A 17" PINE WITH VISIBLE SCRIBING, BEARS N. 87° W., 15.2 FT. FOUND A 24" JUNIPER, WITH VISIBLE SCRIBING, BEARS S 45° W., 17.5 FT.

T. 188 R 31 E
S 32
S 5 | S 4
T 199
PLS 1288
1989

FOUND A 13" x 11" x 10" STONE. FOUND A 30" PINE WITH VISIBLE SCRIBING, BEARS S 71° 50' W., 50.4 FT. FOUND A 32" PINE WITH VISIBLE SCRIBING, BEARS S 55° 51' E., 43.4 FT.

T. 188 R 31 E
1/4
S 5 | S 4
PLS 1288
1989

CORNER WAS RE-ESTABLISHED BY SINGLE PROPORTIONING, N-S, ESTABLISHED NEW B.T.S: A 8" W. FIR BEARS N. 55° 10' E., 30.3 FT SCRIBED "1/4, S. 4, BT". A 10" W. FIR BEARS N 38° W, 38.2 FT SCRIBED "1/4, S 5, BT".

T. 188 R 31 E
S. 5 | S 4
S 8 | S 9
PLS 1288
1989

FOUND A 10" x 14" x 12" STONE FROM WHICH BEARS A 15" PINE, N 77° W., 54.3 FT., A 44" PINE, N 12° E. 27.2 FT, A 16" PINE S 85° 30' E, 63.4 FT, ALL WITH VISIBLE SCRIBING. ESTABLISHED A NEW BT: A 9" PINE BEARS S 35° 10' W, 22.0 FT., SCRIBED "S 8, T 188, R 31 E, BT"

T. 188 R 31 E
1/4 S. 4
S 9
PLS 1288
1989

CORNER WAS RE-ESTABLISHED USING A DIST. - DIST. INTERSECTION USING CALL DISTANCES FROM THE ORIGINAL B.T.S - A 30" PINE BEARS N 61° 30' W, 11.9 FT. (10 LKS) A 20" PINE BEARS S 41° W, 18.5 FT, (28 LKS) - BOTH B.T.S HAVE VISIBLE SCRIBING.

T. 188 R 31 E
1/4
S 8 | S 9
PLS 1288
1989

FOUND A 15" x 12" x 4" MARKED STONE. FOUND A 24" PINE WITH VISIBLE SCRIBING, BEARS N 77° 30' E, 5.3 FT. WITH VISIBLE SCRIBING. ESTABLISHED A NEW B.T. - A 7" JUNIPER BEARS S 02° W, 15.5 FT. SCRIBED "1/4, S 8, BT"

T. 188 R 31 E
C 1/4
PLS 1288
1989

ESTABLISHED BY INTERSECTION OF LINES FROM THE N. AND S. 1/4 SEC. CORNERS AND THE E. AND W. 1/4 SEC. CORNERS. ESTABLISHED NEW B.T.S: A 9" PINE BEARS S 65° 15' W. 27.9 FT SCRIBED "1/4, S 9, BT". A 7" PINE BEARS N. 20° 30' W, 53.8 FT, SCRIBED "1/4, S 9, BT"

T. 188 R 31 E
1/4
S 9 | S 10
PLS 1288
1989

FOUND A 21" x 12" x 7" STONE. FOUND A 32" PINE WITH VISIBLE SCRIBING. BEARS S 71° 25' E, 40.0 FT. FOUND A 20" D. FIR WITH VISIBLE SCRIBING, BEARS S 90° W, 25.5 FT.

T. 188 R 31 E
S 1/16
S 8 | S 9
PLS 1288
1989

ESTABLISHED BY SINGLE PROPORTIONING, N-S, ESTABLISHED NEW B.T.S: A 7" PINE BEARS N. 41° 30' W, 19.8 FT. SCRIBED "1/16, S 9, BT". A 4" PINE BEARS N 67° 30' E, 12.6 FT. SCRIBED "X"

T. 188 R 31 E
S 1/16
S | 9
C
PLS 1288
1989

ESTABLISHED BY SINGLE PROPORTIONING, N-S, ESTABLISHED NEW B.T.S: A 10" PINE BEARS N 60° 10' E, 12.5 FT, SCRIBED "1/16, S 9, BT" A 6" PINE BEARS S 04° 30' W, 11.0 FT. SCRIBED "1/16, S 9, BT"

T. 188 R 31 E
S 1/16
S 9 | S 10
PLS 1288
1989

ESTABLISHED BY SINGLE PROPORTIONING, N-S, ESTABLISHED NEW B.T.S: A 8" JUNIPER BEARS S. 86° 15' W. 19.4 FT. SCRIBED "1/16, S. 9, BT", A 8" JUNIPER BEARS N. 17° 05' E, 29.3 FT. SCRIBED "1/16, S 10, BT"

REGISTERED PROFESSIONAL LAND SURVEYOR <i>Chris T. Palmer</i> OREGON SEPTEMBER 23, 1977 CHRIS T. PALMER 1288	FORKS CADASTRAL SURVEY, "FEICHTMEIR CO-OP" CONTRACT NO. 83-04KK-9-02475		
	CORNER RECORDS PORTION OF T. 188, R 31 E, T. 188, R 31 E, W.M. HARNEY AND GRANT COUNTIES, OREGON		
	Scale: -	Date: JUNE 1989	Job: 1184
	Dsn: Drn: CTP Ckd: CTP	M.A. PALMER & SONS, INC. ENGINEERING & SURVEYING 254 N. Alder - Box 61 Burns, Oregon 97720	Sht. No. 2 of 3