



SURVEY OF MALHEUR NATIONAL FOREST BOUNDARY LINES IN SECTION 6, TOWN- SHIP 16 SOUTH, RANGE 31 EAST, W.M., GRANT COUNTY, OREGON W.O. 88-628~E

SURVEY FOR
U.S.D.A., FOREST SERVICE
MALHEUR NATIONAL FOREST
139 NE. DAYTON STREET
JOHN DAY, OREGON 97845
[503] 575-1731

SURVEY BY
ARMSTRONG SURVEYING
& ENGINEERING, INC.
378 EAST SECOND STREET
PRINEVILLE, OREGON 97754
[503] 447-7791

GENERAL SURVEY NOTES

- BASIS OF BEARINGS.** BEARINGS ARE BASED ON SOLAR OBSERVATION BY THE ALTITUDE METHOD TAKEN AT THE STANDARD 1/4 CORNER ON THE SOUTH LINE OF SEC. 31, T.15S., R.31E., W.M.
- SURVEY INFORMATION~** SEE ACCOMPANYING 2 SHEETS OF CORNER ACCESSORY INFORMATION; ACCOMPANYING CERTIFIED RECORDS OF LAND CORNER MONUMENTATION, 7 SHEETS, AND ATTACHED SURVEY NARRATIVE, 3 SHEETS, FOR ADDITIONAL INFORMATION ON PROCEDURES AND / OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.
- GENERAL LAND OFFICE RECORD FOR TOWNSHIP SUBDIVISIONAL LINES OF T.16S., R.31E., W.M. BY SAMUEL W. LACKLAND, DEPUTY SURVEYOR, UNDER JOINT G.L.O. CONTRACT NO. 357, ALONG WITH BAMFORD ROBB, DEPUTY SURVEYOR, WHO SURVEYED THE WEST TOWNSHIP BOUNDARY UNDER THE SAME CONTRACT DATED JULY 2, 1880, ALL PERFORMED THAT YEAR. G.L.O. RECORD FOR THE THIRD STANDARD PARALLEL SOUTH BY A.O. ECKELSON, DEPUTY SURVEYOR, UNDER JOINT G.L.O. CONTRACT NO. 328 DATED JUNE 20, 1879, AND PERFORMED THAT YEAR.**

LEGEND

- SET 2 1/2" O.D. X 30" LONG ALUMINUM PIPE WITH A 2 1/2" ALUMINUM CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY.
- FOUND 2 1/2" BRASS CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY BY ROBERT D. BAGETT, LS 598, IN 1981.
- FOUND 3 1/4" ALUMINUM CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY BY LELAND L. MYERS, LS 699, IN 1986.
- FOUND 2 1/2" ALUMINUM CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY BY DOUGLAS M. FERGUSON, LS 848, IN 1986.
- [] RECORD SURVEY INFORMATION BY A.O. ECKELSON, IN 1879.
- *[] RECORD SURVEY INFORMATION BY BAMFORD ROBB, IN 1880.
- *[] RECORD SURVEY INFORMATION BY SAMUEL W. LACKLAND, IN 1880.
- > < RECORD SURVEY INFORMATION BY ROBERT D. BAGETT, LS 598, IN 1981, C.S. 681.
- < > RECORD SURVEY INFORMATION BY DOUGLAS M. FERGUSON, LS 848, IN 1986, C.S. 974.
- () RECORD SURVEY INFORMATION BY LELAND L. MYERS, LS 699, IN 1986, C.S. 940.
- INDICATES MALHEUR NATIONAL FOREST BOUNDARY LINE POSTED UNDER THIS CONTRACT WITH 6 FT. LONG STEEL FENCE POSTS WITH NATIONAL FOREST BOUNDARY SIGNS [54-2] ATTACHED.
- (E-5) CORNER MONUMENT NUMBER ~ SEE CORNER SUMMARY FOR ADDITIONAL INFORMATION.
- (S) CORNER METHOD OF RE-ESTABLISHMENT OR REMONUMENTATION FOR CORNERS ORIGINALLY ESTABLISHED BY THE G.L.O.
- E~ ORIGINAL EVIDENCE
- P~ PROPORTIONATE METHOD BY SURVEY
- S~ OTHER REGISTERED LAND SURVEYOR

SURVEYOR'S CERTIFICATE

I, DAVID B. ARMSTRONG, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON DO HEREBY CERTIFY THAT THIS PLAT AND NOTES HEREON OR ATTACHED ARE A CORRECT REPRESENTATION OF A SURVEY I PERFORMED DURING AUGUST-OCTOBER, 1989, AT THE REQUEST OF THE U.S.D.A., FOREST SERVICE, IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON AND THE ARTICLES OF MY CONTRACT.

GULCH CADASTRAL SURVEY
CONTRACT NO. 53-04KK-8-02399
MALHEUR NATIONAL FOREST
BEAR VALLEY RANGER DISTRICT

FOREST SERVICE CERTIFICATES

EXAMINED AND ACCEPTED FOR THE U.S. FOREST SERVICE.

David B. Armstrong 1/23/90
C.O.R. DATE

I CERTIFY THAT THIS SURVEY WAS PERFORMED AT THE REQUEST OF THE MALHEUR NATIONAL FOREST SUPERVISOR.

Ma Gorch 1/23/90
FOREST SUPERVISOR DATE

RECORDATION

RECEIVED AND
FILED
FEB 13 1990
OFFICE OF COUNTY SURVEYOR
JOHN DAY, OREGON

REGISTERED
PROFESSIONAL
LAND SURVEYOR
David B. Armstrong
12/22/89
DAVID B. ARMSTRONG
1025

C.S. 1122

FIELD BOOK 6
W.O. 88-628~E