



**SURVEY OF MALHEUR NATIONAL FOREST BOUNDARY LINES IN SECTIONS 1, 3, & 11, TOWNSHIP 16 SOUTH, RANGE 31 EAST, W.M., AND SECTION 6, TOWNSHIP 16 SOUTH, RANGE 32 EAST, W.M., GRANT COUNTY, OREGON W.O. 88-628~F**

GULCH CADASTRAL SURVEY  
 CONTRACT NO. 53-04KK-8-02399  
 MALHEUR NATIONAL FOREST  
 BEAR VALLEY RANGER DISTRICT

<b>SURVEY FOR</b>	<b>SURVEY BY</b>
U.S.D.A., FOREST SERVICE MALHEUR NATIONAL FOREST 139 N.E. DAYTON STREET JOHN DAY, OREGON 97845 [503] 575-1731	ARMSTRONG SURVEYING & ENGINEERING, INC. 378 EAST SECOND STREET PRINEVILLE, OREGON 97754 [503] 447-7791

- GENERAL SURVEY NOTES**
1. FIELD SURVEY NOTES ARE ON FILE IN THE OFFICE OF ARMSTRONG SURVEYING & ENGINEERING, INC., 378 EAST SECOND STREET, PRINEVILLE, OREGON. FIELD BOOKS 5-9.
  2. BASIS OF BEARINGS. BEARINGS ARE BASED ON SOLAR OBSERVATION BY THE ALTITUDE METHOD TAKEN NEAR THE N1/4 CORNER COMMON TO SECTIONS 10 AND 11.
  3. SURVEY INFORMATION - SEE ACCOMPANYING 3 SHEETS OF CORNER ACCESSORY INFORMATION; ACCOMPANYING CERTIFIED RECORDS OF LAND CORNER MONUMENTATION, 17 SHEETS; AND ATTACHED SURVEY NARRATIVE, 6 SHEETS, FOR ADDITIONAL INFORMATION ON PROCEDURES AND OR CONDITIONS ENCOUNTERED DURING THIS SURVEY.
  4. GENERAL LAND OFFICE RECORD FOR TOWNSHIP SUBDIVISIONAL LINES OF TOWNSHIP 16 SOUTH, RANGE 31 EAST, W.M., BY SAMUEL W. LACKLAND, DEPUTY SURVEYOR, UNDER JOINT G.L.O. CONTRACT NO. 357 DATED JULY 2, 1880, AND PERFORMED THAT YEAR. SUBDIVISIONAL LINES OF TOWNSHIP 16 SOUTH, RANGE 32 EAST, W.M., BY SAMUEL W. LACKLAND, DEPUTY SURVEYOR, UNDER G.L.O. CONTRACT NO. 384 DATED MARCH 29, 1881, AND PERFORMED THAT YEAR. THE RANGE LINE COMMON TO THESE TOWNSHIPS WAS SURVEYED BY BAMFORD ROBB, DEPUTY SURVEYOR, UNDER SAME JOINT G.L.O. CONTRACT NO. 357.

**LEGEND**

- SET 2 1/2" O.D. X 30" LONG ALUMINUM PIPE WITH A 2 1/2" ALUMINUM CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY.
  - FOUND 1 1/2" GALVANIZED IRON PIPE WITH A 2 1/2" BRASS CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY BY ROBERT D. BAGETT, LS 598, IN 1983.
  - FOUND 2 1/2" ALUMINUM PIPE WITH A 3 1/4" ALUMINUM CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY BY GREGORY T. BLACKMAN, LS 991, IN 1982.
  - FOUND 2" ALUMINUM PIPE WITH A 3 1/4" ALUMINUM CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY BY LELAND L. MYERS, LS 699, IN 1986.
  - FOUND 2 1/2" ALUMINUM PIPE WITH A 3 1/4" ALUMINUM CAP MARKED AS PER CORNER DIAGRAM SHOWN ON CORNER SUMMARY BY DOUGLAS M. FERGUSON, LS 848, IN 1987.
- INDICATES MALHEUR NATIONAL FOREST BOUNDARY LINE POSTED UNDER THIS CONTRACT WITH 6 FOOT LONG STEEL FENCE POSTS WITH NATIONAL FOREST PROPERTY BOUNDARY SIGNS C54-21 ATTACHED.
- [ ] RECORD SURVEY INFORMATION BY SAMUEL W. LACKLAND, IN 1880.
- < > RECORD SURVEY INFORMATION BY SAMUEL W. LACKLAND, IN 1881.
- (E-5) CORNER MONUMENT NUMBER - SEE CORNER SUMMARY FOR INFORMATION.
- (S) CORNER METHOD OF RE-ESTABLISHMENT OR REMONUMENTATION FOR CORNERS ORIGINALLY ESTABLISHED BY THE G.L.O.
- E - ORIGINAL EVIDENCE. P - PROPORTIONATE METHOD BY SURVEY. S - OTHER REGISTERED LAND SURVEYOR.
- [ ] CORNER SEARCH - SEARCHED FOR NOT FOUND.

**SURVEYOR'S CERTIFICATE**

I, DAVID B. ARMSTRONG, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF OREGON DO HEREBY CERTIFY THAT THIS PLAT AND NOTES HEREON OR ATTACHED ARE A CORRECT REPRESENTATION OF A SURVEY I PERFORMED DURING AUGUST-NOVEMBER, 1989, AT THE REQUEST OF THE U.S.D.A., FOREST SERVICE, IN ACCORDANCE WITH STATUTES OF THE STATE OF OREGON AND THE ARTICLES OF MY CONTRACT.

REGISTERED PROFESSIONAL LAND SURVEYOR  
 David B. Armstrong  
 12/23/89 OREGON  
 David B. Armstrong  
 1026

**FOREST SERVICE CERTIFICATES**

EXAMINED AND ACCEPTED FOR THE U.S. FOREST SERVICE.

DE Galbraith 1/23/90  
 C.O.R. DATE

I CERTIFY THAT THIS SURVEY WAS PERFORMED AT THE REQUEST OF THE MALHEUR NATIONAL FOREST SUPERVISOR.

Ma en Burke 1/23/90  
 FOREST SUPERVISOR DATE

**RECORDATION**

RECEIVED AND FILED  
 FEB 13 1990  
 OFFICE OF COUNTY SURVEYOR  
 CLATSOP COUNTY, OREGON

C. 5. 1124

SECTION 26, 23, 14 ~ PRIVATE  
 N89°23'16"W ~ 5253.35  
 [ WEST ~ 79.54 CHS. ~ 5249.64 ]  
 [ S89°23'58"E ~ 5253.103 ]  
 [ ] RECORD SURVEY INFORMATION BY ROBERT D. BAGETT, LS 598, IN 1983, C.S. 779.

