

CORNER RECORDS: ALL CORNERS ARE MONUMENTED WITH A 2 1/2" ϕ X 30" LONG ALUM. MON. STAMPED AS SHOWN, ORIGINAL G.L.O. STONE CORNERS ARE BURIED ALONGSIDE THE ALUM. MON. AND A STEEL FENCE POST WITH A 54-9, "SURVEY MONUMENT" ALONGSIDE THE CORNER.

ALL REFERENCE MONUMENTS ARE BEARING TREES HAVING A 6" BAND OF RED PAINT, 54-3 SIGN "BEARING TREE", 54-9 SIGN "SURVEY MONUMENT" AND A BRASS WASHER STAMPED P.L.S 1288.

T 155 R 28 E
1/4 S. 16
S. 21
PLS 1288
1989

FOUND A 13" X 10" X 8" STONE IN A STONE MOUND FROM WHICH A 36" PINE STUMP WITH AXE MARKS BEARS N. 23° 10' E., 47.0 FT. ESTABLISHED NEW BT'S; 8" PINE BEARS S 85° 10' W, 23.3 FT, SCRIBED "1/4, S 21, BT", A 18" PINE BEARS N 32° 45' W, 9.7 FT., SCRIBED "1/4, S 16, BT"

T 155 R 28 E
1/4
S. 20 | S. 21
PLS 1288
1989

FOUND STONE MOUND FROM WHICH A 40" PINE (LINE TREE) BEARS 601° 15' E, 66.6 FT. ESTABLISHED NEW BT'S; 8" JUNIPER BEARS S 23° 00' W, 55.2 FT. SCRIBED "1/4, S 20, BT" A 14" PINE BEARS S 62° 40' E, 68.9 FT. SCRIBED "1/4, S 21, BT"

T 155, R 28 E
1/4 S. 21
S. 20
W.C. 20' 6
PLS 1288
1989

FOUND A SCRIBED PINE BLOWDOWN WHICH BEARS S 02° W, 23 LKS TO THE CORNER. MONUMENT WAS SET 20' S OF THE TRUE CORNER LOCATION. ESTABLISHED NEW BT'S; 8" W. FIR BEARS N 51° 15' E, 51.8 FT. SCRIBED "1/4, S 21, BT" A 14" JUNIPER BEARS S 49° 15' E, 31.1 FT. SCRIBED "1/4, S 28, BT". BOTH BT'S ARE REFERENCED TO THE TRUE CORNER LOCATION.

T. 155, R 28 E
C 1/4
S. 21
PLS 1288
1989

ESTABLISHED BY INTERSECTION OF E-W AND A N-S LINES FROM THE CONTROLLING 1/4 CORNER. ESTABLISHED NEW BT'S; 6" PINE BEARS N. 55° 45' W 11.8 FT. SCRIBED "1/4, S 21, BT". A 8" PINE BEARS S 30° 50' W 13.5 FT. SCRIBED "1/4, S 21, BT"

T. 155, R 28 E
N 1/16
C
PLS 1288
1989

ESTABLISHED AT MID-POINT BETWEEN THE N 1/4 AND C 1/4 CORNERS. ESTABLISHED NEW BT'S; A 10" PINE BEARS S 24° 45' E, 25.3 FT. SCRIBED "1/16, S 21, BT", A 6" PINE BEARS N 64° 55' E, 31.6 FT. SCRIBED "1/16, S 21, BT"

CERTIFICATION:

I, CHRIS T. PALMER, LAND SURVEYOR REGISTERED IN ACCORDANCE WITH THE LAWS OF THE STATE OF OREGON, HEREBY CERTIFY THAT THIS PLAT HEREON IS A TRUE REPRESENTATION OF A SURVEY I PERFORMED IN OCTOBER OF 1989 AT THE REQUEST OF THE U.S. D.A. FOREST SERVICE IN ACCORDANCE WITH THE STATUTES OF THE STATE OF OREGON AND THE TERMS OF OUR CONTRACT.

Chris Palmer

CHRIS T. PALMER, P.L.S.
OREGON LICENCE NO. 1288

APPROVAL

EXAMINED AND ACCEPTED FOR THE
MALHEUR NATIONAL FOREST THIS 17th
DAY OF January 1990.

J. E. Elin
C.O.R.

I CERTIFY THAT THIS SURVEY WAS
PERFORMED AT THE REQUEST OF
THE U.S. FOREST SERVICE.

Mar. G. G. G. 1/17/90
MALHEUR NATIONAL FOREST
SUPERVISOR

RECORDATION:

OFFICE OF THE GRANT COUNTY SURVEYOR,
STATE OF OREGON. I HEREBY CERTIFY THAT
THE WITHIN INSTRUMENT WAS FILED FOR
RECORD ON THIS 30 DAY OF JAN 1990.

COUNTY SURVEY NO. 1126

Robert D. Dyer
GRANT COUNTY SURVEYOR

REGISTERED PROFESSIONAL LAND SURVEYOR <i>Chris Palmer</i> OREGON SEPTEMBER 23, 1977 CHRIS T. PALMER 1288	FORKS CADASTRAL SURVEY "SHAKE" CONTRACT NO. 53-04KK-9-02475 COR. RECORDS, CERT., APPROVAL, RECORDATION PORTION OF SEC. 21, T155, R28E, W.M. GRANT COUNTY OREGON		
	Scale: -	Date: SEPT. 1989	Job: 1184
	Dsn:	M.A.P.'s M. A. PALMER & SONS, INC. ENGINEERING & SURVEYING 254 N. Alder - Box 61 Burns, Oregon 97720	Sht. No.
	Dmn: CTP. Ckd: CTP.		of 2 2

MOS # 1126