



BASIS OF BEARINGS
RECORD MAP OF SURVEY NO.1163

LEGEND

O Set 5/8"x 30" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER.

x—x Fence line.

REFERENCES

Deed Record Book 80 Page 461.

No.	Direction	Length
1	N71°33'54"W	107.35
2	N35°52'56"W	66.19
3	S71°33'54"W	43.95
4	N39°04'44"W	42.74
5	N71°33'54"E	59.02
6	S35°52'56"E	66.19

NARRATIVE: This survey was performed for the Grant County Road Department. The purpose of this survey was to delineate an area for a rock pit on lands of the Homer Barry Hereford Ranch, Inc.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the existing County Road No. 76, as shown hereon. New monuments were set at locations approved by Doug Ferguson, P.E., Bob Kowing, Roadmaster, and Wayne Barry. I tied this survey to the monumented NW corner of section 32.

I determined the location of the right of way lines of County Road No. 76, as per deed, Book 80, Page 461, as shown hereon. The areas shown hereon for the rock pit site are calculated to the approximate centerline of the road as shown.

No.	Delta	Radius	Arc Length	Chord
1	54°34'12"	90.00	85.72	S81°09'00"W 82.52
2	35°40'58"	95.00	59.16	N53°43'25"W 58.21
3	72°33'10"	15.00	18.99	N72°09'31"W 17.75
4	72°33'10"	55.00	69.65	S72°09'31"E 65.08
5	35°40'58"	55.00	34.25	S53°43'25"E 33.70

RECEIVED AND
FILED

JUNE 7, 1991

OFFICE OF COUNTY SURVEYOR

Robert D. Bagett
ATTEST: *[Signature]*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon		
MAP OF SURVEY FOR COUNTY LEASE OF ROCKPIT SITUATED IN THE SE1/4SW1/4, SW1/4SW1/4 SEC.32 T13S, R31E, W.M.		
GRANT COUNTY, OREGON		
SURVEYED FOR	GRANT CO. ROAD DEPT.	
SURVEYED BY	RDB & JLW & GJR	6/3/91
Scale: 1"=100'	Drawn by:	J.L.W.

RECORD MAP OF SURVEY NO.1168.