

NARRATIVE: This survey was performed for the Grant County Road Department. The purpose of this survey was to locate and monument the relocated right of way lines for this portion of County Road No. 19.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the West 1/4 corner and the Northwest corner of section 8, and the proposed realignment of this road. The proposed right of way lines were positioned at locations determined and approved by Doug Ferguson, P.E., and by the road department. The new right of way widths accommodate the cuts and fills necessary for the new construction. The various centerline stations shown are tied to the corners noted above. These corners were monumented in 1969, during Survey No. 154.

The county acquired right of way through part of these private lands via deeds, Book 69, Page 392-394. The old right of way lines shown hereon are based on the deed record. New right of way lines will be acquired for the relocation of this portion of the road. The old road right of way will be vacated for the length of this project only, and will be replaced by the newly acquired right of way shown hereon. My research disclosed that this road may have been part of that old county road described in Commissioner's Journal Book E, Page 121. Although the upper portion of this existing road appears to follow the old alignment, as approved in said Commissioner's Journal, it is obvious that the lower part does not follow it. I am uncertain that the old road as approved is a portion of this existing road, and therefore I do not show the old alignment, the lower portion of which would be off these map sheets.

LEGEND

- Found 5/8" iron pin, of record.
- Set 5/8"x 30" iron pin with attached aluminum cap marked BGA SURVEY MARKER and the centerline road station and distance to centerline.
- x— Fence line
- Found monument from Recorded Survey No. 154. Survey No. appears in the box.

REFERENCES

Deed Record Book 104 Page 64
124 641
133 736
133 740

Instrument No. 920134, 920135

Record Map of Survey No. 154, 155

NOTE:
We drove 6 ft. long galvanized steel fence posts alongside each right of way pin set, where practical.

The section and section subdivisional lines shown are protracted for general information only.

Centerline station -0+15.70 being 418.95 ft. S. and 980.38 ft. E. of the W1/4 corner of section 8, T8S, R30E, W.M., which is monumented with a 1-1/2" iron pipe with attached Grant County Brass Cap.

County Road No. 15

Edge of Existing Road

(To be Vacated)
Deeded Right of Way
(To be Vacated)
Book 69 Page 394

TILLAY AND
P & M CRAFTS, INC.

TILLAY AND
P & M CRAFTS, INC.

T8S, R30E
SECTION 8
SW1/4NW1/4

County Road No. 19

TILLAY AND
P & M CRAFTS, INC.



BASIS OF BEARINGS
SOLAR OBSERVATION

RECEIVED AND
FILED

Feb 28, 1992
OFFICE OF COUNTY SURVEYOR

Robert D. Baggett
ATTEST: *John L. Winters*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Baggett
OREGON
JULY 15, 1983
ROBERT D. BAGGETT
598

SHEET 1 OF 3

BAGETT - GRIFFITH & ASSOCIATES
John Day, Oregon

MAP OF SURVEY
A PORTION OF COUNTY ROAD NO. 19
SITUATED IN THE SW1/4SE1/4, SE1/4 SW1/4 SEC. 8
AND IN SECTION 8, T8S, R30E, W.M.

GRANT COUNTY, OREGON	
SURVEYED FOR	GRANT COUNTY ROAD DEPARTMENT
SURVEYED BY	RDB & JLM & SF & GJR
Scale: 1"=50'	Drawn by: J.L.W.
10/9/91	to 12/23/91

RECORD MAP OF SURVEY NO. 1193.