



BASIS OF BEARINGS
SOLAR OBSERVATION

LEGEND

- Found 5/8" iron pin with attached alum. cap marked BGA SURVEY MARKER, see Record Map of Survey No. 1137.
- Set 5/8"x 30" iron pin with attached alum. cap marked BGA SURVEY MARKER.
- x—x Fence line

REFERENCES

Deed Record Book 81 Page 64
Record Map of Survey No. 1137
Leases and Agreements Book L Page 819.

RECEIVED AND
FILED

Feb 28, 1992
OFFICE OF COUNTY SURVEYOR

Robert D. Baggett

ATTEST: J.L.W.

NOTE:
We drove 6 ft. long galvanized steel fence posts alongside each pin set, where practical.

The section and section subdivisional lines shown are protracted for general information only.

Area is calculated to within 30 ft. of the approx. centerline of County Road No. 14.

NARRATIVE: This survey was performed at the request of Jim Walker, Assistant County Road Supervisor. The purpose of this survey was to delineate an area for a rock pit and rock storage site and a sand storage site lease.
A search was made of the available records pertaining to this survey. Field measurements were made to locate existing monuments which I set during Survey No. 1137. The new monument set during this current survey was set at the location approved by Mr. Walker. The nearest found section corner is the SE corner of Section 36. During Survey No. 1137, I searched for the W1/4 corner, the S1/4 corner and the SW corner of section 35 but found no corner evidence. In the interest of economy, I tied this survey to the known corner at the SE corner of section 36, which is monumented with the original marked stone. I did not determine the right of way lines of County Road No. 14 in this survey. The areas for these two tracts are calculated to within 30 feet of the approximate centerline of the road as located and shown hereon.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

ROBERT D. BAGGETT
598

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon		
MAP OF SURVEY OF PROPOSED LEASE SITE SITUATED IN THE NW1/4SW1/4 AND SW1/4NW1/4 OF SECTION 35, T9S, R30E, W.M.		
GRANT COUNTY, OREGON		
SURVEYED FOR	GRANT COUNTY ROAD DEPARTMENT	
SURVEYED BY	RDB & SDF & NF	2/17/92
Scale: 1"=100'	Drawn by: J.L.W.	