



BASIS OF BEARINGS
RECORD SURVEY NO.771

LEGEND

- ☒ Found 1-1/2" galv. iron pipe with attached Grant County Surveyor Brass Cap.
 - ☒ Found 1-1/2" brass cap grouted into bedrock.
 - ☐ Set 5/8"x 30" iron pin with attached aluminum cap marked BGA SURVEY MARKER, and appropriate corner designation marks.
 - ☐ Found monument from Recorded Survey No. Survey No. appears in the box.
- () Record bearing and distance.

REFERENCES

Instrument No. 910063

Record Map of Survey No. 384, 407, 771.

NARRATIVE: This survey was performed at the request of John Rowlette, contract purchaser of the N1/2NW1/4 Sec. 11, Twp. 14S., R.32E. The purpose of this survey was to subdivide the NW1/4 of said Section 11, and to post the south line of the N1/2NW1/4.

A search was made of the available records pertaining to this survey. Field measurements were made to locate existing controlling monuments, ie, the N1/4 cor., the E1/4 cor., the NW cor., the W1/4 cor., and the C1/4 cor. of Said Sec. 11. I establish the CN1/16 cor. at midpoint between the N1/4 cor. and the C1/4 cor. monuments. I establish the N1/16 cor. on West boundary of Sec. 11 at midpoint between the NW cor. and the W1/4 cor. monuments. We posted the south line of the N1/2NW1/4.

I found no unusual conditions with this survey.

RECEIVED AND
FILED

SEPT 2, 1992
OFFICE OF COUNTY SURVEYOR

ATTEST:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Baggett
OREGON
JULY 12, 1963
ROBERT D. BAGETT
598



BAGETT - GRIFFITH & ASSOCIATES
John Day, Oregon

MAP OF SURVEY
SITUATED IN THE
NW1/4 OF SECTION 11, T14S, R32E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR	JOHN ROWLETTE
--------------	---------------

SURVEYED BY	RDB & SDF & GJR & NIF
-------------	-----------------------

Scale: 1"=500'	Drawn by: J.L.W.
----------------	------------------

8/11/92

RECORD MAP OF SURVEY NO. 1229