



MONUMENTATION AND MAINTENANCE

See standard U.S.F.S. "INDEX No." in the circle on the map. Monuments are stamped as shown below. On each Bearing tree, nailed a brass washer stamped "PLS 848" blaze above the BT scribe and nailed warning signs on the back. Set steel posts with warning and boundary signs, on line within 5 ft. of property corners, or a single post with a warning sign within 5 ft. of controlling corners.

See "CERTIFIED RECORD OF LAND CORNER MONUMENTATION" forms on file in the office of the Grant County Surveyor for a complete history, description of evidence found, monument set, and accessories established at all corners set or maintained.

P-11

T9S R35-1/2E
C 1/4
S21
1992
PLS 848

Ponderosa Pine, 10" dia., bears N71°06'W, 32.3 ft., scribed: C1/4 S21 BT
Ponderosa Pine, 10" dia., bears N05°19'W, 37.3 ft., scribed: C1/4 S21 BT
Lodgepole Pine, 10" dia., bears S74°44'E, 43.8 ft., scribed: C1/4 S21 BT
Ponderosa Pine, 8" dia., bears S11°52'W, 23.6 ft., scribed: C1/4 S21 BT

R-11

T9S R35-1/2E
S21
1/4 — —
S28
1992
PLS 848

Lodgepole pine, 24" dia., bears N73°05'W, 125.0 ft., scribed: 1/4 S21 BT
Lodgepole pine, 20" dia., bears N39°40'W, 142.4 ft., scribed: 1/4 S21 BT
Lodgepole pine, 7" dia., bears S02°27'E, 254.4 ft., scribed: X BT
Lodgepole pine, 10" dia., bears S11°16'W, 269.4 ft., scribed: 1/4 S28 BT

Q-9

T9S
S1/16
S21
R35-1/2E
PLS 1305
1982

Lodgepole Pine, 7" dia., bears S76°15'E, 48.8 ft., scribed: X BT
Lodgepole Pine, 10" dia., bears S17°45'E, 32.9 ft., scribed: S1/16 S21 BT

R-12

T9S R35-1/2E
S21
E1/16 — —
S28
1992
PLS 848

Lodgepole Pine, 8" dia., bears N37°51'E, 92.7 ft., scribed: E1/16 S21 BT
Lodgepole Pine, 10" dia., bears S89°57'E, 79.9 ft., scribed: E1/16 S28 BT

Q-11

T9S R35-1/2E
C
S1/16 S21
C
1992
PLS 848

Lodgepole pine, 24" dia., bears S58°30'W, 207.0 ft., scribed: C-S 1/16 S21 BT
Lodgepole pine, 24" dia., bears N04°08'E, 287.0 ft., scribed: C-S 1/16 S21 BT

T-11

T9S R35-1/2E
C 1/4
S28
1992
PLS 848

Douglas Fir, 14" dia., bears N80°22'W, 27.9 ft., scribed: C1/4 S28 BT
Douglas Fir, 10" dia., bears N24°39'W, 27.4 ft., scribed: C1/4 S28 BT
Lodgepole Pine, 8" dia., bears S69°11'E, 38.8 ft., scribed: C1/4 S28 BT
Ponderosa Pine, 22" dia., bears S09°56'E, 106.4 ft., scribed: C1/4 S28 BT

Q-12

T9S R35-1/2E
SE 1/16
S21
1992
PLS 848

Lodgepole pine, 12" dia., bears N61°39'E, 97.2 ft., scribed: SE 1/16 S21 BT
Lodgepole pine, 10" dia., bears S77°18'E, 98.7 ft., scribed: SE 1/16 S21 BT

T-12

T9S R35-1/2E
E 1/16
C — — C
S28
1992
PLS 848

Spruce, 14" dia., bears N81°57'E, 166.4 ft., scribed: C-E 1/16 S28 BT
Lodgepole Pine, 10" dia., bears S16°46'W, 113.9 ft., scribed: C-E 1/16 S28 BT

R-9

T9S R35E S25
T9S S21
S28
R35-1/2E
1974
(BLM Brass Cap)

Lodgepole pine, 8" dia., bears S14°45'E, 24.4 ft., scribed: T9S R35-1/2E S28 BT

