



BASIS OF BEARINGS
 Record Map of Survey No. 330

LEGEND

- Found 3/4" iron rod set by Oregon State Hwy Dept., no record.
- Found 5/8" iron pin, see Record Map of Survey No. 330
- Set 5/8"x 30" iron pin with attached aluminum cap marked BGA SURVEY MARKER and the centerline road station
- () Record bearing and distance.

REFERENCES

Record Map of Survey No. 330
 Deed Record Book 111 Page 123
 115 877
 Oregon State Highway Dept. Drawing No. 5B-11-10

NOTE:
 Set pin offset N23°56'10"E, 0.70 feet from calculated right of way intersect point, Highway station 161+39.50 and County Road No. 53 station 314+16.15.

NARRATIVE: This survey was performed at the request of Jim Walker, Assistant County Road Supervisor, acting in behalf of the Grant County Road Department. The purpose of this survey was to locate and monument new relocated right of way lines for a portion of the northern end of County Road No. 53, as shown hereon. The additional right of way width is needed for road widening and slope protection. The county acquired the right of way for this portion of County Road No. 53 by deed, as recorded in Deeds, Book 111, Page 123 and Book 115, Page 877.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the south 1/4 corner of Section 30 and appurtenant monuments along the existing right of way. The new right of way monuments were set at locations determined and approved by Mr. Walker.

RECEIVED AND
 FILED

July 26, 1993
 OFFICE OF COUNTY SURVEYOR

Robert D. Baggett
 ATTEST: *Steven D. Follweiler*

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Robert D. Baggett
 OREGON
 JULY 12, 1983
 ROBERT D. BAGGETT
 598
 Expiration Date 12/31/94

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon		
MAP OF SURVEY PORTION OF COUNTY ROAD NO. 53 SITUATED IN THE SE1/4SE1/4 SEC. 19 AND NE1/4NE1/4 SEC. 30, T13S, R32E, W.M.		
GRANT COUNTY, OREGON		
SURVEYED FOR	GRANT COUNTY ROAD DEPARTMENT	
SURVEYED BY	RDB & SDF & GJR	5/10/93
Scale: 1"=50'	Drawn by: J.L.W.	

RECORD MAP OF SURVEY NO. 1256