



BASIS OF BEARINGS
SOLAR OBSERVATION

- LEGEND
- Found 2-1/2" alum. pipe with attached alum. cap.
 - Found 5/8" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER.
 - Set 5/8" x 30" iron pin with attached aluminum cap marked BGA SURVEY MARKER and the centerline road station and distance to centerline.
 - Record bearing and distance.
 - Fence line.
 - Found Monument from Recorded Survey No. Survey No. appears in box.

NARRATIVE: This survey was performed at the request of Jim Walker, Assistant County Road Supervisor, acting in behalf of the Grant County Road Department. The purpose of this survey was to locate and monument proposed new relocated right of way lines for a portion of County Road No. 18, as shown hereon. The additional right of way width is needed for road widening and slope protection. The county acquired a 60 foot right of way for this portion of County Road No. 18 by deed, as recorded in Deed Records: Book 92, Page 511, Book 94, Page 646, Book 95, Page 116, and Book 95, Page 117.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the existing road and the supporting cuts and fills. Also, to locate the NW corner of Section 21, the SE corner of Section 21, the S1/16 corner of Section 21 and 22, and appurtenant monuments from Survey No.s 890 and 1288. New right of way monuments were set at locations approved by Mr. Walker, and Charles Barn of the County Road Department.

REFERENCES

Record Map of Survey No. 634, 890
Deed Record Bk 46 Pg 25-26
46 553
48 501
92 511
94 426
94 646
95 116-118
Instrument No. 901308
911824
County Court Probate No. 1368

NOTES:

We drove 6 ft. long galvanized steel fence posts alongside each right of way pin set, where practical.

The section and section subdivision lines shown are protracted for general information only.

RECEIVED AND FILED
DEC. 30, 1993
OFFICE OF COUNTY SURVEYOR
Robert D. Bagett
ATTEST: Jeremy Russell

REGISTERED PROFESSIONAL LAND SURVEYOR
ROBERT D. BAGETT
JULY 12, 1983
598
Renewal Date 12/31/94

SHEET 1 OF 3

BAGETT - GRIFFITH & ASSOCIATES
John Day, Oregon

MAP OF SURVEY
PROPOSED RIGHT OF WAY
OF A PORTION OF COUNTY ROAD NO. 18
SITUATED IN THE SW1/4SW1/4 SEC. 17
AND NE1/4N1/2NW1/4 SEC. 20 AND
SE1/4N1/2SW1/4, S1/2NW1/4 SEC. 21 T10S, R31E, W.M.
GRANT COUNTY, OREGON

SURVEYED FOR	GRANT COUNTY ROAD DEPARTMENT
SURVEYED BY	RDB & SDF & GJR & DEM
Scale: 1"=100'	Drawn by: J.L.W.

10/20/93