

NORTH FORK JOHN DAY GPS CONTROL SURVEY
FOR
UMATILLA NATIONAL FOREST
LOCATED IN
TOWNSHIP 6 SOUTH, RANGES 34 & 35 EAST,
TOWNSHIP 7 SOUTH, RANGES 34 & 35 EAST,
AND
TOWNSHIP 8 SOUTH, RANGES 31 & 33 EAST,
WILLAMETTE MERIDIAN
GRANT & UMATILLA COUNTIES
OREGON
SEPTEMBER THROUGH OCTOBER 1993

CORNER INFORMATION

9301

JANIS 1989 (T. 6 S., R. 34 E., SECTION 13)

FOUND A 3 1/4 INCH ALUMINUM CAP ON A 3/4 INCH ALUMINUM ROD, PROJECTING 1/2 INCH OUT OF A ROCK OUTCROP, MARKED AS SHOWN.

9302

WINDM CREEK 1993 (T. 6 S., R. 34 E., SECTION 28)

SET A 3 1/4 INCH ALUMINUM CAP, ON A 5/8 BY 36 INCH REBAR, FLUSH WITH THE GROUND, MARKED AS SHOWN, FROM WHICH;

A METAL FENCE POST WITH LSM (LAND SURVEY MONUMENT) SIGN BEARS, WEST, 4.0 FEET.

9303

CORNER OF SECTIONS 29, 30, 31 & 32, T. 6 S., R. 34 E.

FOUND A 2 1/2 INCH ALUMINUM CAP, ON A 2 1/2 INCH ALUMINUM PIPE, PROJECTING 1 INCH OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH;

9" LODGEPOLE PINE BEARS, N.20 1/2°E., 83.7 FEET, SCRIBING 'T6S R34E S29°BT' VISIBLE ON DOUBLE BLAZE, WITH 3/4" DIAMETER BRASS WASHER STAMPED 'PLS 1636' NAILED TO LOWER BLAZE BY THE 'BT' SCRIBING.

A DOWN & DECAYED LODGEPOLE PINE'S ROOT HOLE BEARS, N.24°E., 68.6 FEET, WITH SCRIBING VISIBLE (ORIGINAL BT).

7" LODGEPOLE PINE BEARS, S.31°E., 43.1 FEET, SCRIBING 'T6S R34E S32°BT' VISIBLE ON DOUBLE BLAZE, WITH 3/4" DIAMETER BRASS WASHER STAMPED 'PLS 1636' NAILED TO LOWER BLAZE BY THE 'BT' SCRIBING.

8" LODGEPOLE PINE BEARS, S.84 1/2°W., 58.4 FEET, SCRIBING 'T6S R34E S31°BT' VISIBLE ON DOUBLE BLAZE, WITH 3/4" DIAMETER BRASS WASHER STAMPED 'PLS 1636' NAILED TO LOWER BLAZE BY THE 'BT' SCRIBING.

8" LODGEPOLE PINE BEARS, N.44°W., 76.3 FEET, SCRIBING 'T6S R34E S30°BT' VISIBLE ON DOUBLE BLAZE, WITH 3/4" DIAMETER BRASS WASHER STAMPED 'PLS 1636' NAILED TO LOWER BLAZE BY THE 'BT' SCRIBING.

A DOWN & DECAYED LODGEPOLE PINE'S ROOT HOLE BEARS, N.22 3/4°E., 49.5 FEET (ORIGINAL BT).

9304

WINDM CREEK NO.2 1993 (T. 6 S., R. 34 E., SECTION 33)

SET A 3 1/4 INCH ALUMINUM CAP, ON A 5/8 BY 36 INCH REBAR, FLUSH WITH THE GROUND, MARKED AS SHOWN, FROM WHICH;

A METAL FENCE POST WITH LSM SIGN BEARS, SOUTH, 4.0 FEET.

9305

CORNER OF SECTIONS 26, 27, 34 & 35, T. 6 S., R. 34 E.

FOUND A 2 1/2 INCH ALUMINUM CAP, ON A 2 1/2 INCH ALUMINUM PIPE, PROJECTING 4 INCHES OUT OF THE GROUND IN A SMALL RING OF STONE, MARKED AS SHOWN, FROM WHICH;

7" DOWNED LODGEPOLE PINE'S ROOT HOLE BEARS, N.34°E., 9.9 FEET, SCRIBING 'T6S R34E S26 BT' VISIBLE (ORIGINAL BT).

10" WESTERN LARCH BEARS, N.85 1/2°E., 44.8 FEET, SCRIBING 'T6S R34E S26°BT' VISIBLE ON DOUBLE BLAZE, WITH 3/4" DIAMETER BRASS WASHER STAMPED 'PLS 1636' NAILED TO LOWER BLAZE BY THE 'BT' SCRIBING.

A DOWN AND DECAYED LODGEPOLE PINE'S ROOT HOLE BEARS, S.44°E., 23.8 FEET, SCRIBING VISIBLE (ORIGINAL BT).






13" WESTERN LARCH BEARS, S.74°E., 25.5 FEET, SCRIBING 'T6S R34E S35°BT' VISIBLE ON DOUBLE BLAZE, WITH 3/4" DIAMETER BRASS WASHER STAMPED 'PLS 1636' NAILED TO LOWER BLAZE BY THE 'BT' SCRIBING.

7" DOWNED LODGEPOLE PINE'S ROOT HOLE BEARS, S.58°W., 17.8 FEET, SCRIBING 'T6S R34E S34 BT' VISIBLE (ORIGINAL BT).

16" WESTERN LARCH BEARS, S.43 1/4°W., 60.1 FEET, SCRIBING 'T6S R34E S34°BT' VISIBLE ON DOUBLE BLAZE, WITH 3/4" DIAMETER BRASS WASHER STAMPED 'PLS 1636' NAILED TO LOWER BLAZE BY THE 'BT' SCRIBING.

8" LODGEPOLE PINE SNAG BEARS, N.69°W., 17.2 FEET, SCRIBING 'T6S R34E S27 BT' VISIBLE.

11" WESTERN LARCH BEARS, N.18 1/2°W., 28.1 FEET, SCRIBING 'T6S R34E S27°BT' VISIBLE ON DOUBLE BLAZE, WITH 3/4" DIAMETER BRASS WASHER STAMPED 'PLS 1636' NAILED TO LOWER BLAZE BY THE 'BT' SCRIBING.



9306

BURN 1989 (T. 6 S., R. 35 E., SECTION 34)

FOUND A 3 1/4 INCH ALUMINUM CAP, ON A 3/4 INCH ALUMINUM ROD, PROJECTING 4 INCHES OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH;

A METAL FENCE POST WITH ATTENTION SIGN BEARS, N.24°E., 3.4 FEET.

9307

CORNER OF SECTIONS 2, 3, 34 & 35, T. 6 & 7 S., R. 34 E.

FOUND A 2 1/2 INCH ALUMINUM CAP, ON A 2 1/2 INCH ALUMINUM PIPE, PROJECTING 24 INCHES OUT OF THE GROUND, SET IN A STONE MOUND 3 1/2 FEET IN DIAMETER BY 19 INCHES HIGH, MARKED AS SHOWN, FROM WHICH;

8" PONDEROSA PINE BEARS N.33°E., 17.1 FEET, SCRIBING 'T6S R34E S35 BT' VISIBLE ON PARTIALLY HEALED BLAZE, WITH A 3/4 INCH DIAMETER BRASS WASHER MARKED 'RPLS 1910' NAILED TO THE BLAZE BY THE 'BT' SCRIBING.

A STONE MOUND, 2 1/2 FEET IN DIAMETER BY 16 INCHES HIGH, BEARS N.80 1/4°E., 71.5 FEET.

29" PONDEROSA PINE SNAG BEARS N.83 1/2°E., 107.3 FEET, SCRIBING 'T6S R34E S2 BT' VISIBLE ON PARTIALLY HEALED DOUBLE BLAZE (ORIGINAL BT).

10" DOUGLAS FIR BEARS S.89°E., 73.7 FEET, SCRIBING 'T6S R34E S2 BT' VISIBLE ON PARTIALLY HEALED BLAZE, WITH A 3/4 INCH DIAMETER BRASS WASHER MARKED 'RPLS 1910' NAILED TO THE BLAZE BY THE 'BT' SCRIBING.

38" PONDEROSA PINE BEARS S.63°W., 103.6 FEET, SCRIBING '4E S3' VISIBLE ON PARTIALLY CUT OPENED BLAZE (ORIGINAL BT).

24" DOWNED PONDEROSA PINE SNAG BEARS N. 65° W., 124.7 FEET, DOUBLE BLAZED WITH SCRIBING 'T6S R34E S34' VISIBLE ON UPPER BLAZE (ORIGINAL BT).

11" DOUGLAS FIR BEARS N.43°W., 65.7 FEET, SCRIBING 'T6S R34E S34 BT' VISIBLE ON PARTIALLY HEALED BLAZE, WITH A 3/4 INCH DIAMETER BRASS WASHER MARKED 'RPLS 1910' NAILED TO THE BLAZE BY THE 'BT' SCRIBING.

9308

1/4 CORNER OF SECTIONS 2 & 11, T. 7 S., R. 34 E.

FOUND A 2 1/2 INCH ALUMINUM CAP, ON A 2 1/2 INCH ALUMINUM PIPE, PROJECTING 6 INCHES OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH;

12" LODGEPOLE PINE BEARS N.80°E., 22.9 FEET, SCRIBING '1/4 S2°BT' VISIBLE ON PARTIALLY HEALED DOUBLE BLAZE, WITH A 3/4 INCH DIAMETER BRASS WASHER MARKED 'RPLS 1910' NAILED TO THE LOWER BLAZE BY THE 'BT' SCRIBING.

8" LODGEPOLE PINE BEARS S.1°E., 44.7 FEET, SCRIBED WITH AN 'X' ON BLAZE 4 1/2 FEET ABOVE GROUND AND 'BT' ON LOWER BLAZE, WITH A 3/4 INCH DIAMETER BRASS WASHER MARKED 'RPLS 1910' NAILED TO THE LOWER BLAZE BY THE 'BT' SCRIBING.

9309

CORNER OF SECTIONS 11, 12, 13 & 14, T. 7 S., R. 35 E.

FOUND A 2 1/2 INCH ALUMINUM CAP, ON A 2 1/2 INCH ALUMINUM PIPE, PROJECTING 1 INCH OUT OF THE GROUND SET IN A RING OF STONE 2 FEET IN DIAMETER, MARKED AS SHOWN, FROM WHICH;

13" LODGEPOLE PINE BEARS, N.53 1/2°E., 124.6 FEET, SCRIBED 'T7S R35E S12 BT' ON SINGLE BLAZE (RECORD N.55°E.).





13" DOWNED LODGEPOLE PINE SNAG, BEARS S.88°E., 13.2 FEET, SCRIBING VISIBLE ON CHOPPED OPEN BLAZE (ORIGINAL BT).

18" LODGEPOLE PINE BEARS, N.80 1/2°W., 83.3 FEET, SCRIBED 'T7S R35E S11 BT' ON SINGLE BLAZE (RECORD 83.7 FEET).

10" LODGEPOLE PINE SNAG BEARS, N.31 3/4°W., 12.9 FEET, SCRIBING 'T7S R35E S11 BT' ON PARTIALLY HEALED BLAZE (RECORD N.30°W., 12.5 FEET) (ORIGINAL BT).

A 1 1/2 INCH ALUMINUM CAP, ON A 5/8 INCH REBAR, SET FLUSH WITH THE GROUND, MARKED 'S13 12.00 FT 1106' BEARS, S.20°22'E., 12.04 FEET (RECORD S.17 1/2°E., 12.00 FEET).

A 1 1/2 INCH ALUMINUM CAP, ON A 5/8 INCH REBAR, PROJECTING 1 INCH OUT OF THE GROUND, MARKED 'S14 12.00 FT 1106' BEARS, S.42°45'W., 12.04 FEET (RECORD S.46°W., 12.00 FEET).



9310

NE 1/16 CORNER OF SECTION 24, T. 7 S., R. 35 E.

FOUND A 2 1/2 INCH ALUMINUM CAP, ON A 2 1/2 INCH ALUMINUM PIPE, PROJECTING 4 INCHES OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH;

A 1 1/2 INCH ALUMINUM CAP, ON A 5/8 INCH REBAR, PROJECTING 2 INCHES OUT OF THE GROUND, MARKED 'S24 12.00 FT 1106', BEARS N.42°E., 12.0 FEET.

A 5/8 INCH REBAR, PROJECTING 4 INCHES OUT OF THE GROUND, BEARS N.42 1/2°W., 12.0 FEET.

9311

MOON MEADOW NO.1 1993 (T. 7 S., R. 35 E., SECTION 30)

SET A 3 1/4 INCH ALUMINUM CAP, ON A 5/8 BY 36 INCH REBAR, FLUSH WITH THE GROUND, MARKED AS SHOWN, FROM WHICH;

A METAL FENCE POST WITH WILDERNESS BOUNDARY & LSM SIGNS BEARS, S.27°E., 3.0 FEET.

9312

MOON MEADOW NO.2 1993 (T. 7 S., R. 35 E., SECTION 30)

SET A 3 1/4 INCH ALUMINUM CAP, ON A 5/8 BY 36 INCH REBAR, FLUSH WITH THE GROUND, MARKED AS SHOWN, FROM WHICH;

A METAL FENCE POST WITH WILDERNESS BOUNDARY & LSM SIGNS BEARS, S.55°W., 3.2 FEET.

9313

BENCH MARK N 11-43 (T. 8 S., R. 31 E., SECTION 19)

FOUND A 2 1/2 INCH BRASS DISK SET IN CONCRETE FLUSH WITH THE GROUND, MARKED AS SHOWN.

9314

BULL PRAIRE 1993 (T. 8 S., R. 33 E., SECTION 13)

SET A 3 1/4 INCH ALUMINUM CAP, ON A 5/8 BY 36 INCH REBAR, FLUSH WITH THE GROUND, MARKED AS SHOWN, FROM WHICH;

A METAL FENCE POST WITH LSM SIGN BEARS, EAST, 4.0 FEET.

