



BASIS OF BEARINGS

SOLAR OBSERVATION

TAKEN 1100' WEST OF W1/4 COR. SEC.18 T10S,R28E

LEGEND

- Found 5/8" Iron pin with attached aluminum cap marked BGA SURVEY MARKER and the centerline road station and distance to centerline, see Map of Survey No. 1196.
- Set 5/8"x30" Iron pin with attached aluminum cap marked BGA SURVEY MARKER and the centerline road station and distance to centerline.
- x—x Fence line

REFERENCES

Record Map of Survey No.'s 920, 1157, 1196
 Deed Record Agreements Bk I Pg 260
 84 300
 84 314
 84 316
 84 320

NARRATIVE: This survey was performed at the request of Bob Kowing, Road Supervisor, acting in behalf of the Grant County Road Department. The purpose of this survey was to locate and monument the proposed right of way lines for County Road 7, as shown hereon.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the existing road and certain section and 1/4 section corners, as shown hereon.

The proposed right of way lines are basically positioned 30 feet each side of the existing centerline of this road. Additional right of way widths accommodate the existing cuts and fills. These proposed right of way lines were approved by Mr. Kowing. Selected centerline stations are tied to the nearest found government corners, as shown.

In 1960 the various land owners along this road agreed to grant road right of way to the county if the county would survey, describe and improve the road. The county improved the road but never followed through with the survey, the descriptions or any deed acquisition of right of way. Deeds will be prepared with centerline descriptions agreeing with this map in order that the present owners of the lands may deed the rights of way.

I researched all the County Commissioner Journals, but could not positively identify any approved road which generally followed this alignment.

RECEIVED AND FILED

JULY 20, 1994
OFFICE OF COUNTY SURVEYOR

Robert D. Baggett

ATTEST: Jeremy Russell

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Baggett
 OREGON
 JULY 12, 1983
 ROBERT D. BAGGETT
 598
 Renewal Date 12/31/94

SHEET 1 OF 7

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon	
MAP OF SURVEY OF PROPOSED COUNTY ROAD NO. 7 SITUATED IN THE SW1/4 SEC.35, T9S,R28E AND IN THE NE1/4, SE1/4 SEC.13, T10S, R27E AND IN THE NW1/4 SEC.2; SE1/4; SW1/4 SEC.3; SE1/4; SW1/4 SEC.4; SE1/4; SW1/4 SEC.5; NE1/4; SE1/4 SEC.7; NW1/4 SEC.8; NE1/4; SW1/4; NW1/4 SEC.16 T9S,R28E,W.M. GRANT COUNTY, OREGON	
SURVEYED FOR	GRANT COUNTY ROAD DEPARTMENT
SURVEYED BY	RDB & SDF & GJR & DEM & RJL
Scale: 1"=1000'	Drawn by: J.L.W.
Feb. 1993 to July 1994	

RECORD MAP OF SURVEY NO.1312