



BASIS OF BEARINGS
RECORD MAP OF SURVEY NO. 762
AS SHOWN

- LEGEND**
- Found 5/8" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER.
 - Found 1/2" iron pin with attached yellow plastic cap.
 - Set 5/8"x30" iron pin with attached yellow plastic cap marked BGA SURVEY MARKER.
 - () Record bearing and distance
 - X—X Fence line.
 - Found Monument from Recorded Survey No. Survey No. appears in box.
- REFERENCES**
- Record Map of Survey No.'s 324, 357, 568, 569, 762, 805, 1243
- Deed Record Bk 101 Pg 243
111 377-378
112 118-119
116 567-570
124 610
- Deed Record Instrument No. 810704
910790
931168
932528

NARRATIVE: This survey was performed at the request of Bob Kowing, Road Supervisor, acting in behalf of the Grant County Road Department. The purpose of this survey was to locate and monument the proposed right of way lines for this portion of County Road 74.

A search was made of the available records pertaining to this survey. Field measurements were made to locate certain section corners and 1/4 corners, as shown, and the proposed alignment of this road. The right of way lines were positioned at locations approved by Doug Ferguson, P.E., and by Mr. Kowing of the road department. The right of way widths accommodate the cuts and fills necessary for new construction. Various centerline stations are tied to the section and 1/4 section corners as shown hereon.

NOTE: We drove 6 ft. long galvanized steel fence posts alongside each right of way pin set, where practical.

RECEIVED AND
FILED
April 29, 1994
OFFICE OF COUNTY SURVEYOR
Robert D. Baggett
ATTEST: Steven D. Follweiler

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Robert D. Baggett
JULY 12, 1983
OREGON
ROBERT D. BAGGETT
598
Renewal Date 12/31/94

SHEET 1 OF 2

BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon		
MAP OF SURVEY PROPOSED COUNTY ROAD NO. 74 SITUATED IN THE NE1/4 AND SE1/4 SEC. 34 T13S, R31E AND IN GOVT LOT 3 AND THE NE1/4SW1/4 SEC. 2 T14S, R31E, W.M.		
GRANT COUNTY, OREGON		
SURVEYED FOR	GRANT COUNTY ROAD DEPARTMENT	
SURVEYED BY	RDB & SDF & GJR & DEM	3/1/94
Scale: 1"=100'	Drawn by:	J.L.W.

RECORD MAP OF SURVEY NO. 1313