

T7S R29E
Section 36

Point being 270.29 ft. S. and
1599.16 ft. E. of the NW corner
of Section 36, T7S, R29E, W.M.
The NW corner of Section 36 is
monumented with a 1½" iron pipe
with attached Grant County Surveyor
brass cap.

RUTH ROSS

NE1/4NW1/4

Proposed Rock Quarry Site
3.72 Acres

Proposed Rock Storage Site
1.41 Acres

COUNTY ROAD NO. 15

NW1/4NW1/4

BASIS OF BEARINGS

SOLAR OBSERVATION
TAKEN 1900' EAST OF NW CORNER SEC.36

LEGEND

○ Set 5/8"x30" iron pin with attached aluminum
cap marked BGA SURVEY MARKER.

REFERENCES

Grant County Deed Records Book 138 Page 763.

NARRATIVE: This survey was performed at the request of Jim Walker, Assistant County Road Supervisor, acting in behalf of the County Road Department. The purpose of this survey was to delineate an area for a rock quarry lease site and rock storage site. Also, we were to locate the existing access road leading from this site to County Road No. 15.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the existing access road and the NW corner of Section 36, which I remonumented from original evidence. New monuments were set at locations approved by Mr. Walker, as shown hereon. I found no unusual conditions during this survey.

NOTE: We drove 6 ft. long galvanized
steel fence posts alongside each pin
set, where practical.

NOTE: The section and section subdivisional
lines shown are protracted for general
information only.

RECEIVED AND
FILED


Aug 3, 1994
OFFICE OF COUNTY SURVEYOR

Robert D. Baggett
ATTEST: J. L. Waters

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Baggett
OREGON
JULY 12, 1963
ROBERT D. BAGGETT
598

Renewal Date 12/31/94

 BAGETT - GRIFFITH & ASSOCIATES John Day, Oregon		
MAP OF SURVEY PROPOSED ROCK PIT LEASE SITE AND ACCESS ROAD SITUATED IN THE NW1/4 SECTION 36 T7S, R29E, W.M.		
GRANT COUNTY, OREGON		
GRANT COUNTY ROAD DEPARTMENT		
SURVEYED FOR	RDB & SDF & DEM & RJL	
SURVEYED BY	J.L.W.	6/20/94
Scale: 1"=100'	Drawn by:	J.L.W.

RECORD MAP OF SURVEY NO.1332