

**SURVEY FOR
UMATILLA NATIONAL FOREST
OF
AP-3256 TO AP-3257
NORTH FORK JOHN DAY UNIT
NORTH FORK JOHN DAY WILDERNESS
LOCATED ON
THE SECTION LINE BETWEEN SECTIONS 7 & 18
T. 8 S., R. 34 E., W.M.
GRANT COUNTY, OREGON
JULY - AUGUST, 1995**

9422
CORNER OF SECTIONS 29, 30, 31 & 32, T. 8 S., R. 34 E.

FOUND A 2 1/2" ALUMINUM PIPE, WITH 3 1/4" ALUMINUM CAP, PROJECTING 14" OUT OF THE GROUND AND SURROUNDED BY A STONE MOUND, MARKED AS SHOWN, FROM WHICH:

45" WESTERN LARCH, N. 55 1/2" E., 33.8 FEET, SCRIBING "T8S R34E S29"BT" VISIBLE ON A DOUBLE BLAZE (1993 BT).
36" DOUGLAS FIR SNAG, S. 43 1/2" E., 38.9 FEET, WITH HEALED BLAZE (ORIGINAL BT).
10" ENGLEMANN SPRUCE, S. 22 3/4" E., 9.5 FEET, SCRIBING "T8S R34E S32"BT" VISIBLE ON A DOUBLE BLAZE (1993 BT).
10" LODGEPOLE PINE, S. 31 1/2" W., 28.0 FEET, SCRIBING "T8S R34E S31"BT" VISIBLE ON A DOUBLE BLAZE (1993 BT).
31" DOUGLAS FIR SNAG, S. 80 1/4" W., 23.8 FEET, WITH NO MARKS VISIBLE (ORIGINAL BT).
32" DOUGLAS FIR, N. 77" W., 35.6 FEET, WITH HEALED DOUBLE BLAZE (ORIGINAL BT).


THE 1993 BT'S HAVE A 3/4" BRASS WASHER STAMPED "RLS 2308" NAILED TO THE LOWER BLAZE BETWEEN THE "BT" SCRIBING.

9423
CORNER OF SECTIONS 12 & 13, T. 8 S., R. 33 E. AND SECTIONS 7 & 18, T. 8 S., R. 34 E.

FOUND A 2 1/2" ALUMINUM PIPE, WITH 3 1/4" ALUMINUM CAP, PROJECTING 6" OUT OF THE GROUND AND SURROUNDED BY A STONE MOUND, MARKED AS SHOWN, FROM WHICH:

9" WINDTHROWN LODGEPOLE PINE SNAG, N. 21" E., 31.7 FEET, WITH ILLEGIBLE SCRIBING VISIBLE ON A PARTIALLY HEALED BLAZE (ORIGINAL BT).
5" WESTERN LARCH, N. 51" E., 48.9 FEET, SCRIBING "T8S R34E S7"BT" VISIBLE ON DOUBLE BLAZE (1992 BT).
11" WINDTHROWN LODGEPOLE PINE SNAG, S. 51" E., 20.5 FEET, WITH ILLEGIBLE SCRIBING VISIBLE ON A PARTIALLY HEALED BLAZE (ORIGINAL BT).
12" WESTERN LARCH, S. 23 1/2" E., 24.4 FEET, SCRIBING "T8S R34E S18"BT" VISIBLE ON DOUBLE BLAZE (1992 BT).
11" WINDTHROWN LODGEPOLE PINE SNAG, S. 47" W., 39.6 FEET (ORIGINAL BT).
15" WESTERN LARCH, S. 73" W., 44.4 FEET, SCRIBING "T8S R34E S13"BT" VISIBLE ON DOUBLE BLAZE (1992 BT).
21" WESTERN LARCH, N. 69" W., 11.1 FEET, WITH HEALED BLAZE (ORIGINAL BT).

THE 1992 BT'S HAVE A 3/4" BRASS WASHER STAMPED "RLS 2308" NAILED TO THE LOWER BLAZE BETWEEN THE "BT" SCRIBING.



9517
1/4 CORNER OF SECTIONS 19 & 20, T. 8 S., R. 34 E.

FOUND A 2 1/2" ALUMINUM PIPE, WITH 3 1/4" ALUMINUM CAP, PROJECTING 6" OUT OF THE GROUND AND SURROUNDED BY A STONE MOUND, MARKED AS SHOWN, FROM WHICH:

9" LODGEPOLE PINE, N. 28" E., 28.8 FEET, SCRIBING "1/4 S20"BT" VISIBLE ON A DOUBLE BLAZE (1994 BT).
18" WESTERN LARCH, S. 83 3/4" E., 47.6 FEET, SCRIBING "1/4 S20"BT" VISIBLE ON A DOUBLE BLAZE (1994 BT).
22" DOUGLAS FIR, S. 5" W., 11.9 FEET, WITH A HEALED BLAZE (ORIGINAL BT).
9" LODGEPOLE PINE, N. 42" W., 46.4 FEET, SCRIBING "1/4 S19"BT" VISIBLE ON A DOUBLE BLAZE (1994 BT).



THE 1994 BT'S HAVE A 3/4" BRASS WASHER STAMPED "PLS 1636" NAILED TO THE SCRIBED "B" ON THE LOWER BLAZE.

9518
1/4 CORNER OF SECTIONS 7 & 8, T. 8 S., R. 34 E.

FOUND A 2 1/2" ALUMINUM PIPE, WITH 3 1/4" ALUMINUM CAP, PROJECTING 4" OUT OF THE GROUND AND SURROUNDED BY A STONE MOUND, MARKED AS SHOWN, FROM WHICH:

8" DEAD WINDTHROWN LODGEPOLE PINE, N. 52" E., 15.2 FEET, SCRIBING "1/4 S"BT" VISIBLE ON A DOUBLE BLAZE (ORIGINAL BT).
16" WESTERN LARCH, N. 63" E., 17.5 FEET, SCRIBING "1/4 S8"BT" VISIBLE ON A DOUBLE BLAZE (1994 BT).
25" WESTERN LARCH, S. 65 1/2" E., 25.0 FEET, SCRIBING "1/4 S8"BT" VISIBLE ON A DOUBLE BLAZE (1994 BT).
24" WESTERN LARCH, S. 77" W., 13.7 FEET, SCRIBING "1/4 S7"BT" VISIBLE ON A DOUBLE BLAZE (1994 BT).
15" DEAD WINDTHROWN LODGEPOLE PINE, N. 42" W., 13.9 FEET, SCRIBING "1/4 S BT" VISIBLE ON A FIRE CHARRED BLAZE WITH CHAINING NOTCH BETWEEN THE SCRIBING (ORIGINAL BT).
9" WHITE FIR, N. 38" W., 43.7 FEET, SCRIBING "1/4 S7"BT" VISIBLE ON A DOUBLE BLAZE (1994 BT).

THE 1994 BT'S HAVE A 3/4" BRASS WASHER STAMPED "PLS 1636" NAILED TO THE SCRIBED "B" ON THE LOWER BLAZE.



9519
1/4 CORNER OF SECTIONS 7 & 18, T. 8 S., R. 34 E.

SET BY SINGLE PROPORTION A 2 1/2" BY 30" ALUMINUM PIPE, WITH A 3 1/4" ALUMINUM CAP, 15" IN THE GROUND SURROUNDED BY A STONE MOUND 2' DIAMETER BY 16" HIGH, MARKED AS SHOWN, FROM WHICH:

20" ENGLEMANN SPRUCE, N. 1 3/4" E., 40.3 FEET, SCRIBED "1/4 S7"BT".
7" WHITE FIR, S. 61 3/4" E., 12.7 FEET, SCRIBED "1/4 S18"BT".
17" ENGLEMANN SPRUCE, S. 19 1/4" W., 42.4 FEET, SCRIBED "1/4 S18"BT".
15" WESTERN LARCH, N. 19 1/2" W., 41.6 FEET, SCRIBED "1/4 S7"BT".

9520
CORNER OF SECTIONS 7, 8, 17 & 18, T. 8 S., R. 34 E.




SET BY DOUBLE PROPORTION A 2 1/2" BY 30" ALUMINUM PIPE, WITH A 3 1/4" ALUMINUM CAP, 21" IN THE GROUND, MARKED AS SHOWN, FROM WHICH:

7" LODGEPOLE PINE, N. 40 1/4" E., 8.9 FEET, SCRIBED "T8S R34E S8"BT".
6" LODGEPOLE PINE, S. 35" E., 9.8 FEET, SCRIBED "T8S R34E S17"BT".
10" LODGEPOLE PINE, S. 76" W., 3.5 FEET, SCRIBED "T8S R34E S18"BT".
9" LODGEPOLE PINE, N. 41 1/4" W., 14.7 FEET, SCRIBED "T8S R34E S7"BT".

9521
AP-3256

SET IN A SMALL CREEK ON THE SECTION LINE BETWEEN SECTIONS 7 & 18, A 5/8" BY 24" REBAR, WITH A 3 1/4" ALUMINUM CAP, 20" IN THE GROUND, MARKED AS SHOWN, FROM WHICH:

23" WESTERN LARCH, N. 57 1/4" E., 44.8 FEET, SCRIBED "WB/3256"BT".
17" WESTERN LARCH, N. 22" W., 33.9 FEET, SCRIBED "WB/3256"BT".



REGISTERED
PROFESSIONAL
LAND SURVEYOR

David A. Schlaich

OREGON
JULY 16, 1987
DAVID A. SCHLAICH
2308

RENEWS 06/30/96