



Scale 1"=1000'

BASIS OF BEARINGS

SOLAR OBSERVATION

Taken 500' East of the SW corner of Section 9

- LEGEND**
- Found 1 1/2" iron pipe with attached Grant County Surveyor brass cap. See Corner Restoration records.
 - ⊙ Set 2 1/2" aluminum pipe with attached 2 1/2" aluminum cap. See Corner Restoration records filed in the County Surveyor's office.
 - () GLO record bearing and distance.
 - SFNF Searched For Not Found.
 - NSF Not Searched For.

NARRATIVE:

This survey was performed at the request of T.G. Brown. The purpose of this survey was to locate and flag several section lines which will be fenced.

After searching the available records pertaining to this survey, I found that the NW corner of Section 3, the SW corner of Section 7 and the SE corner of Section 10 have been remonumented from original evidence by the Grant County Surveyor. The SW corner of Section 3 is lost and was remonumented by double proportion. We found original GLO corner evidence at the W1/4 of Section 3 and at the W1/4 corner of Section 15. After searching for the S1/4 corner and the SE corner of Section 3 and finding no evidence, we ran 1/2 mile east and recovered the original bearing trees at the S1/4 corner of Section 2. Then returning to the SE corner of Section 3 we found the original corner stone. We searched for each corner west, along the south line of sections 4 and 5. Utilizing the original topo calls we recovered the original corner stone at the SW corner of Section 5. Then running east we also recovered the S1/4 corner of Section 5, but could find no evidence of the corners on the south boundary of Section 4. The SW corner of Section 10 is also lost and was remonumented by double proportion as shown hereon.

This survey was performed with a Topcon GTS-4 total station, with a closed loop random traverse. I used a IBM compatible AST Bravo 486 computer and CG Survey software to perform the calculations. Refer to the Land Corner Monumentation sheets filed in the office of the Grant County Surveyor for the details of each corner set in this survey.

RECEIVED AND
FILED

NOV 1 1996

OFFICE OF COUNTY SURVEYOR

[Signature]

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]

OREGON
SEPT 19, 1995
JACK L. WATSON
2734

Renewal Date 6/30/98

CORNERSTONE SURVEYING, Inc. 233 S. Canyon Blvd., John Day, Oregon (541) 875-1813	
MAP OF SURVEY DEPENDENT RESURVEY SITUATED IN SECTIONS 2, 3, 7, 8, 9, 10, AND 15, T18S, R28E, W.M.	
GRANT COUNTY, OREGON	
SURVEYED FOR:	T.G. BROWN AND IZEE RANCH
SURVEYED BY :	Carl Stout & Jack Watson Date: 10/21/96
DRAWN BY :	Jack Watson