SURVEY FOR UMATILLA NATIONAL FOREST SMALL TRACTS 061409 & 061410 LOCATED IN SECTIONS 10 AND 11 T. 9 S., R. 35 E., W.M. GRANT COUNTY, OREGON JULY, 1997

BLAINE CORNER NUMBER 7 - MS 342

SET A 5/8" BY 24" REBAR, WITH A 3 1/4" ALUMINUM CAP, FLUSH WITH THE GROUND, MARKED AS SHOWN, FROM WHICH:

8" PONDEROSA PINE, N. 78 1/4" E., 51.0 FEET SCRIBED "MS 342 B7" "BT". 11" DOUGLAS FIR, S. 22" E., 16.3 FEET SCRIBED "MS 342 B7" "BT".



FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP MISS-STAMPED AS BLAINE CORNER NO. 7, PROJECTING 13" OUT OF THE GROUND AND SURROUNDED BY A RING STONE. I REMOVE THE MARKINGS ON THE CAP WHICH REFER TO BLAINE CORNER NO. 7 AND AMEND THE CAP AS SHOWN, FROM WHICH:



## RED BOY CORNER NUMBER 1 - MS 342

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP. PROJECTING 3" OUT OF THE GROUND AND SURROUNDED BY A RING OF STONE, MARKED AS SHOWN, FROM WHICH:

16" DEAD DOUGLAS FIR, S. 68" W., 22.0 FEET WITH HEALED BLAZE.

18" WIND THROWN PONDEROSA PINE SNAG, N. 24" W., 20.2 FEET 18" DOUGLAS FIR, S. 20 3/4" E., 30.7 FEET WITH SCRIBING VISIBLE.

# MINERAL WONDER CORNER NUMBER 4 - MS 637

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, PROJECTING 1" OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH:

18" DOUGLAS FIR, N. 32 3/4" E., 80.8 FEET WITH SCRIBING VISIBLE. 3" PONDEROSA PINE, N. 1° E., 16.7 FEET WITH SCRIBING VISIBLE.

## MINERAL WONDER CORNER NUMBER 3 - MS 637

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, PROJECTING 3" OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH:

18" DOUGLAS FIR. N. 26 1/2" E., 111.7 FEET WITH SCRIBING VISIBLE. 13" PONDEROSA PINE, N. 10 1/4° E., 48.3 FEET WITH SCRIBING VISIBLE.

MINERAL WONDER CORNER NUMBER 2 - MS 637

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, PROJECTING 8" OUT OF THE GROUND, SURROUNDED BY A RING OF STONE, MARKED AS SHOWN, FROM WHICH:

7" WESTERN LARCH, S. 2° E., 11.2 FEET WITH SCRIBING VISIBLE. 6" WHITE FIR, S. 74 1/2" W., 77.0 FEET WITH HEALED BLAZES.

BLAINE RED BOY RLS 2308 (1997 SERVICE)

8761

KED BOX COK

MINERAL WONDER CORNER NUMBER 1 - MS 637

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP. PROJECTING 6" OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH:

10" LODGEPOLE PINE, S. 7 3/4" E., 82.3 FEET WITH SCRIBING VISIBLE.

MINERAL WONDER WITNESS POINT - MS 637

SET A 2 1/2" BY 30" ALUMINUM PIPE, WITH A 3 1/4" ALUMINUM CAP, 24" IN THE GROUND, MARKED AS SHOWN. FROM WHICH:

12" DOUGLAS FIR, N. 48° E., 5.2 FEET, SCRIBED "WP S11" "BT". " WESTERN LARCH, N. 32 1/4° W., 11.2 FEET, SCRIBED "WP S10" "BT".

# CLIMAX WITNESS POINT - MS 342

SET A 2 1/2" BY 30" ALUMINUM PIPE, WITH A 3 1/4" ALUMINUM CAP, 19" IN THE GROUND, MARKED AS SHOWN, FROM WHICH:

6" ENGLEMANN SPRUCE, N. 17" E., 27.9 FEET SCRIBED "WP S11" "BT 5" WHITE FIR, N. 12 3/4" W., 6.0 FEET SCRIBED "WP S10" "BT".

## CLIMAX CORNER NUMBER 1 - MS 342 GOLDEN MONARCH CORNER NUMBER 1 - MS 342

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, PROJECTING 1" OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH:


20" WESTERN LARCH, S. 35° E., 10.0 FEET WITH HEALED BLAZES. 22" WESTERN LARCH, N. 86° E., 22.1 FEET WITH HEALED BLAZES.


#### GOLDEN MONARCH NORTH CENTER END - MS 342

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS NO. 6, PROJECTING 1" OUT OF THE GROUND AND SURROUNDED BY A RING STONE. I REMOVE THE MARKINGS ON THE CAP WHICH REFER TO RED BOY CORNER NO. 6 AND AMEND THE CAP AS SHOWN, FROM WHICH:

"LS 1106" NAILED TO THE LOWER BLAZE.

20" DOUGLAS FIR, N. 62° E., 67.2 FEET WITH SCRIBING VISIBLE ON DOUBLE BLAZE. 18" DEAD DOUGLAS FIR, N. 24° E., 66.6 FEET WITH SCRIBING VISIBLE ON DOUBLE BLAZE AND WITH A BRASS WASHER STAMPED





1978

TOS R35E PZ

MINERAL

WONDER.

MS 637/WP

全 S10 S11

RLS 2308 13/ 1997 15-

FOREST STATES

S10 | S11

CLIMAX RLS 2308 1997 1997 1997

MON CO

MS 342

FOUND THE REMAINS OF A POST 4" SQUARE BY 8" LONG SET FLUSH WITH GROUND, WITH AXE MARKS VISIBLE. IN PLACE OF THE POST I SET A 5/8" BY 24" REBAR, WITH A 3 1/4" ALUMINUM CAP, FLUSH WITH THE GROUND,

4" PONDEROSA PINE, N. 17" E., 34.2 FEET, SCRIBED "MS342 RB6" "BT". 10" PONDEROSA PINE, S. 85° W., 10.5 FEET, SCRIBED "MS342 RB6" "BT".

## CLIMAX CORNER NUMBER 2 - MS 342

MARKED AS SHOWN, FROM WHICH:

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP. PROJECTING 8" OUT OF THE GROUND. SURROUNDED BY A STONE MOUND, MARKED AS SHOWN, FROM WHICH:

7" FIR STUMP, S. 84° E., 63.3 FEET. 15" FIR STUMP, N. 83 1/2° E., 60.6 FEET, WITH SCRIBING VISIBLE. 18" ENGLEMANN SPRUCE, N. 89" E., 61.5 FEET, WITH SCRIBING 15" WIND THROWN DEAD LODGEPOLE PINE, N. 22 1/2° E.,

# POOR BOY MILL SITE CORNER NO. 1 - MS 650B

135.9 FEET, WITH SCRIBING VISIBLE.

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, PROJECTING 10" OUT OF THE GROUND, SURROUNDED BY A STONE MOUND, MARKED AS SHOWN, FROM WHICH:

11" LODGEPOLE PINE, S. 83° E., 60.2 FEET, WITH SCRIBING VISIBLE. 12" LODGEPOLE PINE, N. 22 1/2" W., 61.3 FEET, WITH SCRIBING VISIBLE.

## POOR BOY MILL SITE CORNER NO. 4 - MS 650B


FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, PROJECTING 4" OUT OF A STONE MOUND, 3' IN DIAMETER BY 6" HIGH, SET IN A LARGE TAILINGS PILE, MARKED AS SHOWN, FROM WHICH.

RM, 2" IRON PIPE WITH 3" BRASS CAP. N. 27 1/2° W., 25.4 FEET, STAMPED "RM POOR BOY MS COR 4 25.36FT MS 650B".
RM, 2" IRON PIPE WITH 3" BRASS CAP, S. 41 1/2" W., 31.9 FEET, STAMPED "RM POOR BOY MS COR4 31.88FT MS 650B".

## POOR BOY MILL SITE CORNER NO. 2 - MS 650B

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, SET FLUSH WITH THE GROUND, MARKED AS SHOWN, FROM WHICH:

12" LODGEPOLE PINE SNAG (6' HIGH), N. 9° E., 60.2 FEET. WITH SCRIBING VISIBLE. 12" PONDEROSA PINE, N. 66° W., 11.6 FEET, WITH SCRIBING VISIBLE.



RED BOY 6

MONARCH RLS 2308

tanico.

1 300

COB 5 X

, POOR BOY M.S.

8059 SM

CAP, PROJECTING 2" OUT OF THE EDGE OF A TAILINGS PILE, MARKED AS SHOWN, FROM WHICH: RM, 2" IRON PIPE WITH 3" BRASS CAP,

S. 49 1/2° W., 28.8 FEET, STAMPED "RM POOR BOY MS COR 3 28.78 FT MS 650B". RM, 2" IRON PIPE WITH 3" BRASS CAP, N. 35° W., 75.2 FEET, STAMPED "RM POOR BOY MS COR 3 MS 650B 75.26 FT".

#### GOLDEN CORNER NUMBER 3 - MS 368 MINERAL CHIEF CORNER NUMBER 4 - MS 650A MINERAL WONDER CORNER NUMBER 9 - MS 637

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, PROJECTING 12" OUT OF THE GROUND SURROUNDED BY A STONE MOUND, 3' DIAMETER BY 6" HIGH, MARKED AS SHOWN, FROM WHICH:

12" LODGEPOLE SNAG (6' HIGH), N. 11 1/2" W., 34.4 FEET, WITH 12" PONDEROSA PINE, S. 47° W., 33.7 FEET, WITH SCRIBING VISIBLE.

### POOR BOY CORNER NUMBER 5 - MS 650A MINERAL CHIEF CORNER NUMBER 3 - MS 650A

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, PROJECTING 1" OUT OF THE GROUND, MARKED AS SHOWN, FROM WHICH:

9" LODGEPOLE PINE, S. 42° E., 73.0 FEET, WITH SCRIBING VISIBLE. 12" LODGEPOLE PINE, S. 31 1/2" E., 74.0 FEET, WITH SCRIBING

# POOR BOY ANGLE POINT - MS 650A


SET A 2 1/2" BY 30" ALUMINUM PIPE, WITH A 3 1/4" ALUMINUM CAP, 18" IN THE GROUND SURROUNDED BY A ROCK MOUND 2' IN DIAMETER BY 1' HIGH, MARKED AS SHOWN, FROM WHICH:


RM, 2 1/2" IRON PIPE WITH 3" BRASS CAP, N. 63°23' W.. 71.5 FEET. STAMPED "RM POOR BOY MS COR 3 MS 650B 75.26 FT"

# POOR BOY CORNER NUMBER 4 - MS 650A

FOUND A 2 1/2" IRON PIPE, WITH 3" BRASS CAP, SET FLÚSH WITH THE GROUND, IN A MOUND OF STONES, MARKED AS SHOWN, FROM WHICH:

RM, 2" IRON PIPE WITH 3" BRASS CAP, N. 31 1/4° W., 34.5 FEET, STAMPED "RM POOR BOY COR 4 MS 650A 34.45 FT".
RM, 2" IRON PIPE WITH 3" BRASS CAP, N. 70° E., 27.9 FEET, STAMPED "RM POOR BOY COR 4 MS 650A 27.94 FT".





8791 A

MINERAL C COR

MINERAL W. COR 91

MZ 368

GOLDEN GON

