



NARRATIVE

THIS SURVEY WAS PERFORMED AT THE REQUEST OF ROBERT LONGO. THE PURPOSE OF THIS SURVEY WAS TO SET THE CENTER-SOUTH 1/16 CORNER AND TO POST THE N-S CENTER OF SECTION LINE FROM THIS 1/16 CORNER TO THE NORTH 1/4 CORNER OF SECTION 11.

A SEARCH WAS MADE OF THE AVAILABLE RECORDS PERTAINING TO THIS SURVEY. FIELD MEASUREMENTS WERE MADE TO LOCATE EXISTING CONTROLLING MONUMENTS OF SAID SEC. 11, AS SHOWN HEREON.

I HAD PREVIOUSLY ESTABLISHED THE C1/4 CORNER, THE CSN1/64 CORNER DURING RECORD SURVEY NO. 771 AND THE CN1/16 CORNER DURING RECORD SURVEY NO. 1229.

I ESTABLISH THE CS1/16 COR. AT MIDPOINT BETWEEN THE FOUND S1/4 COR. AND THE C1/4 COR. MONUMENTS. WE POSTED THE N-S CENTER OF SECTION LINE FROM THE CS1/16 CORNER TO THE NORTH 1/4 CORNER WITH LATH.

I FOUND NO UNUSUAL CONDITIONS WITH THIS SURVEY.



BASIS OF BEARINGS

RECORD MAP OF SURVEY NO. 1453

REFERENCES

RECORD MAP OF SURVEY NO.'S 384, 771, 1229 AND 1453

LEGEND

- FOUND 1 1/2" GALV. IRON PIPE WITH ATTACHED GRANT COUNTY SURVEYOR BRASS CAP.
- ⊙ FOUND 1 1/2" BRASS CAP GROUTED INTO BEDROCK
- FOUND 5/8" IRON PIN WITH ATTACHED ALUMINIUM CAP MARKED BGA SURVEY MARKER. (UNLESS OTHERWISE NOTED.)
- SET 5/8"x30" IRON PIN WITH ATTACHED ALUMINIUM CAP MARKED BGA SURVEY MARKER, AND WITH APPROPRIATE 1/16 CORNER DESIGNATION.
- () RECORD BEARING AND/OR DISTANCE - MOS 1453
- (()) RECORD BEARING AND/OR DISTANCE - MOS 771 & 1229
- FOUND MONUMENT FROM RECORDED SURVEY NO. □ SURVEY NO. APPEARS IN BOX.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Bagett

OREGON
JULY 12, 1983
ROBERT D. BAGETT
598
Renewal Date 12/31/99

RECEIVED AND
FILED

July 15, 1998
OFFICE OF COUNTY SURVEYOR

Robert D. Bagett

ATTEST: *Steven D. Fidlmeier*

BAGETT, GRIFFITH & BLACKMAN 217 N. Canyon Blvd. John Day, Oregon		
MAP OF SURVEY SITUATED IN THE E1/2 OF SECTION 11, T.14S., R.32E., W.M. GRANT COUNTY, OREGON		
SURVEYED FOR	ROBERT LONGO	
SURVEYED BY	RDB, SDF & MCS	7/2/98
Scale: 1"=500'	Drawn by: MCS	

RECORD MAP OF SURVEY NO. 1484