



Scale 1"=500'

BASIS OF BEARINGS

SOLAR OBSERVATION
Taken near S1/4 Section 28

LEGEND

- Found 1½" iron pipe with attached 2" brass cap
See Survey No. 7G.
- ⊙ Set 2½" aluminum pipe with attached
2½" aluminum cap.
- x—x Fence Line
- () Record bearing and distance.

NARRATIVE

This survey was performed at the request of Wayne Howard. The purpose of this survey was to establish the C1/4 corner of Section 32, and flag the property lines for fencing..

After searching the available records pertaining to this survey, I found that the controlling corners of Section 28 were remonumented by Vernon Glaze in 1914, see survey number 7G. I found all the controlling corners of Section 28 with the exception of the S1/4 corner. The S1/4 corner was set at single proportion between the SW and the SE corners of Section 28. The C1/4 corner was established at the intersection of the center of section lines.

RECEIVED AND
FILED

JUL 15 1990

OFFICE OF COUNTY SURVEYOR
Attest: *[Signature]*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
SEPT 19, 1995
JACK L. WATSON
2734

Renewal Date 6/30/2000



CORNERSTONE SURVEYING, Inc.

233 S. Canyon Blvd., John Day, Oregon
(541) 575-1813

MAP OF SURVEY
DEPENDANT RESURVEY AND SUBDIVISION
OF SECTION 28, T12S, R28E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR: **Wayne Howard**

SURVEYED BY : Jack Watson

Date: 6/5/98

DRAWN BY : Jack Watson

MAP OF SURVEY NO. 1485