



Scale 1"=200'

BASIS OF BEARINGS

Record Map of Survey No. 131

LEGEND

- Found 2½" iron pipe with attached 3" BLM brass cap, see Record Map of Survey No. 131.
- Set 5/8"x30" iron pin with attached 2" aluminum cap marked as shown.
- X—X Fence Line
- () Record bearing and distance.

NARRATIVE

This survey was performed at the request of Eric Nansen. The purpose of this survey was to establish the W1/16 corner as shown hereon.

After searching the available records pertaining to this survey, I found a BLM resurvey of the township line recorded as Survey No. 131 in the office of the Grant County Surveyor. I found and accepted the BLM monuments at the N1/4 corner and the NW corner of Section 1. I set the W1/16 corner on line and at the mid point between these two corners. A Land Corner Monumentation form has been recorded giving the history and details of the corner accessories for the W1/16 corner.

RECEIVED AND
FILED

AUG 6 1999

OFFICE OF COUNTY SURVEYOR
Attch: *[Signature]*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
SEPT 19, 1995
JACK L. WATSON
2734
Renewal Date 6/30/2000



CORNERSTONE SURVEYING, Inc.

233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY
SITUATED IN THE SW1/4 OF SECTION 36, T9S, R27E AND
IN THE NW1/4 OF SECTION 1, T10S, R27E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR: **ERIC NANSEN**

SURVEYED BY : Jack Watson

Date: 08/03/99

DRAWN BY : Jack Watson

MAP OF SURVEY NO. 1521