



Scale 1"=500'

BASIS OF BEARINGS

SOLAR OBSERVATION
Taken Near NW Corner Section 8

LEGEND

- Found 1" galv. iron pipe with attached 2 1/2" brass cap of Record.
- Found 1 1/2" galv. iron pipe with attached 2 1/2" Grant County Surveyor brass cap.
- Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC.
- ⊙ Set 2" aluminum pipe with attached 3 1/2" alum. cap. See Land Corner Monumentation sheet.
- 1() 1880 GLO record bearing and distance.
- 2() 1939 BLM record bearing and distance.
- 3() Map of Survey No. 815 record bearing and distance.
- Found monument, see record map of survey number shown in box.

NARRATIVE:

This survey was performed at the request of Shawn Moles. The purpose of this survey was to establish the corners of Mr. Moles property as described in Deed Instrument No. 991557.

After searching the available records pertaining to this survey, I found a survey performed by George Rigby in 1939 for the BLM. Also Survey No. 407, which shows the W1/4 and N1/4 corners of Section 9 remonumented by the Grant County Surveyor in 1976. I accepted the corners as shown hereon.

I found the original marked corner stone at the E1/4 corner of Section 5 and remonumented it's position. The NE corner and the N1/4 corner of Section 8 were searched for, but no evidence of these corners was found. The position of the NE corner of Section 8 was determined by doubled proportion, no monument was set. The N1/4 corner of Section 8 was established by single proportion and Section 8 was subdivided to establish the corners of Mr. Moles property.

RECEIVED AND
FILED

NOV 24 1999
OFFICE OF COUNTY SURVEYOR
Attest: *[Signature]*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
SEPT 19, 1995
JACK L. WATSON
2734
Renewal Date 6/30/2000



CORNERSTONE SURVEYING, Inc.
233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY Dependant Resurvey and Subdivision of Section 8 T14S, R32E, W.M.	
GRANT COUNTY, OREGON	
SURVEYED FOR: Shawn Moles	
SURVEYED BY : Jack Watson & Mike Ribeiro Date: 11/12/99	
DRAWN BY : Jack Watson	

MAP OF SURVEY NO. 1536