



BASIS OF BEARINGS

SOLAR OBSERVATION
Taken at the NE 1/4 corner

LEGEND

- Found 2 1/2" aluminum pipe with attached 3" aluminum cap of Record. See Land Corner Monumentation Sheet.
- Set 5/8"x30" iron pin with attached 2" alum. cap, unless otherwise shown, cap marked as shown. See Land Corner Monumentation Sheets for details.
- ◎ Set 2 1/2" aluminum pipe with attached 3" alum. cap. See Land Corner Monumentation Sheets for details.
- () Record bearing and distance.

NARRATIVE

This survey was performed at the request of Roger Lang. The purpose of this survey was to establish and monument the boundaries of Mr. Lang's property as described in Deed Instrument No. 993302.

After searching the available records pertaining to this survey, I found Record Land Corner Monumentation sheets for the SE and NE corners of Section 34. These two corners had been remonumented from original evidence on July 8, 1999.

I found the original corner stones at the NW and SW corners of Section 34 and remonumented them. I found no evidence at any of the four 1/4 corners and set them using the single proportionate measurement method. The section was subdivided in the usual manner and the corners of Mr. Lang's property were established.

RECEIVED AND
FILED
2000
JAN 4, 1999
CLERK OF COUNTY SURVEYOR
JACK L. WATSON

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Jack L. Watson
OREGON
SEPT 19, 1995
JACK L. WATSON
2734
Renewal Date 6/30/2000

| | |
|---|----------------|
| CORNERSTONE SURVEYING, Inc. 233 S. Canyon Blvd., John Day, Oregon 97845 (541) 575-1813 | |
| MAP OF SURVEY DEPENDENT RESURVEY AND SUBDIVISION OF SECTION 34, T12S, R29E, W.M. | |
| GRANT COUNTY, OREGON | |
| SURVEYED FOR: ROGER LANG | |
| SURVEYED BY : Jack Watson | Date: 12/27/99 |
| DRAWN BY : Jack Watson | |

MAP OF SURVEY NO. 1540