



Scale 1"=200'

BASIS OF BEARINGS

SOLAR OBSERVATION

Taken near the N1/4 corner of Section 28

LEGEND

- Set 5/8"x30" iron pin with attached 2" alum. cap marked CORNERSTONE SURVEYING, INC. See corner restoration records for remonumentation details.
- ⊙ Set 2 1/2" aluminum pipe with attached aluminum cap. See corner restoration records for remonumentation details.
- () GLO record bearing and distance.

NARRATIVE

This survey was performed at the request of Gordon Lemons. The purpose of this survey was to establish the east line of the SE1/4 of Section 28.

I made a search of the available records pertaining to this survey. Several corners have been recovered and remonumented in Section 28. I recovered the original corner stone at the E1/4 corner and positioned the SE section corner at record distance from the GLO topo calls north and west of the corner. I set the S1/16 corner on line and at the mid-point between these two corners.

RECEIVED AND
FILED

APRIL 22, 2001
OFFICE OF COUNTY SURVEYOR
RECEIVED

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jack L. Watson
OREGON
SEPT 19, 1995
JACK L. WATSON
2734

Renewal Date 6/30/2002



CORNERSTONE SURVEYING, Inc.

233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY
ESTABLISH THE EAST LINE OF THE SE1/4
OF SECTION 28, T18S, R28E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR: **GORDON LEMONS**

SURVEYED BY : Jack Watson

Date: 04/05/2001

DRAWN BY : Jack Watson

MAP OF SURVEY NO. 1597