

In order to depict a graphical relationship between Surveys 785, 1601 & 1607, a counter-clockwise rotation of 00°03'16" was applied to Map of Survey 1601. This rotation was calculated based on an average comparison of the ties shown on Map of Survey 1601 to the monuments set on Map of Survey 785 and the inverse between these monuments as shown on Map 785. A clockwise rotation of 00°03'09" was applied to Map of Survey 1607. This rotation was calculated based on the comparison of the tie shown on Map of Survey 1607 to the South 1/4 of Section 32 set on Map of Survey 1525(Ferguson) and the bearing shown between these monuments on Map 1185, which is the same as the bearing as shown on Survey 785. For clarity, no rotation is applied to the record bearings as shown on this plat.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
#848

Renewal Date 12/31/01

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 13, 1899
KENNETH H. DELANO JR.
#49865

Renewal Date 12/31/01

RECEIVED AND
FILED

SEPT. 6, 2001
OFFICE OF COUNTY SURVEYOR
Robert D. Baxet
Attest: Michael C. Sprague

MAP OF SURVEY NO. 1609