

Jack returned Mike Kilpatrick to his office.

We proceeded to Corner (C). S12-S13-/S7-S18, T.13S., R.30 & 31E.

Jack showed us a basalt stone that he recovered from a mound of stone surrounding his aluminum pipe monument. Jack said he found this stone lying loose on the ground with three other stones. This stone measures 13x11x6 inches. I saw on the stone two notches on one edge which may possibly be chisel marks. One looked better than the other. I saw no other marks on the stone. The section corner stone should be marked with two notches on the north edge and 4 notches on the south edge.

We proceeded to Corner (D). Corner of T.12 & 13S., R.30 & 31E.

There has been no evidence of the original corner found. Doug Ferguson set this corner at proportionate measure for easting control and near the creek for northing control in his 1983 Survey No. 785. Jack showed us Doug's monument.

Doug indicated that he believed the two alder trees taken by John B. David, the GLO surveyor who originally set this corner, could not grow in the double proportion position. He said he looked at this situation in 1983 and decided there was no evidence of a spring near enough to support the alder BT's. He decided to set the township corner very close to the creek.

Jack showed us his double proportionate position, an aluminum pipe and cap, approximately S.20°E., 120 feet from Doug's position. He also showed us the remains of a tree, badly decayed and level with the ground. Jack said someone from the Forest Service told him this was a hardwood tree and could only grow very near to water.

We proceeded to Corner (E). 1/4 corner S32-S5 T.12 & 13S., R.31E.

Jack showed us his aluminum pipe and a basalt stone measuring 19x7x5 inches which he said was the original 1/4 corner stone. I saw no marks on this stone. I asked Jack to point the marks out to me. He pointed to what I believe are natural features of the stone. I do not believe that this is the 1/4 corner stone.

As we started to leave, Jack called to me and asked if I had gotten the message to hold off filing his map of survey. I told him I would not file it yet. He said if he and Doug worked out a compromise that he may yank his monument out of the ground at this 1/4 corner and not use it. Jack picked up his map and corner restoration sheets the next day, June 20th.