

two 4 inch diameter alder bearing trees for this corner, each 8 links from the corner. The monument that Doug set in 1982 is at the south bank of the creek where alder trees would grow and are still growing there.

The monument that Jack showed us for his double proportioned corner is uphill and about 120 feet southerly of the creek. I saw no evidence of a spring or alder trees. The remains of the tree Jack showed us has not been positively identified as to species at this time.

CONCLUSION:

Inconclusive evidence that the township corner position monumented by Doug in 1982 should be moved to the position monumented by Jack.

Corner (E): 1/4 S32-S5, T.12 & 13S., R.31E.

I saw no chisel marks on this stone. We had bright sunshine all day. I turned the stone several times to catch the shadows on the stone to see any marks. I asked Jack to show me the 1/4 marks he said he found. He pointed to natural features on the stone.

CONCLUSION:

I do not believe that this is the 1/4 corner stone.

Robert D. Baggett

Robert D. Baggett, PLS

**RECEIVED AND
FILED**

SEPT. 6, 2001
OFFICE OF COUNTY SURVEYOR
Robert D. Baggett
Attest: *Michael A. Spang*

MAP OF SURVEY NO. 1609