

appeared to be two man-made notches on one edge. The stone was found on a rather steep hillside in an area that showed clear indications of sliding rocks and soil.

Opinion: Inconclusive evidence. To be properly marked, the stone should have displayed two notches on one edge and four on an opposite edge. Only two possible man-made notches were found, meaning it is inconclusive that the stone was the same as marked in the original survey. Because of the area being unstable, it is not possible to say that the stone was found in its original position.

3) The Corner of Sections 7, 12, 13, and 18, Tps. 13 S., Rs. 30 and 31 E., W. M., Oregon.

Original record by John B. David, in 1869: "Set stone 16x8x6 for corner to secs. 7, 12, 13, and 18."

This corner was determined to be lost by Doug Ferguson, RLS, while performing a contract for the Forest Service from 1981-83. Ferguson reestablished the corner by single proportionate measurement but did not monument it. Recently, Jack Watson, RLS, while performing a survey for a private land owner, reported finding the original corner stone.

Findings: The alleged corner stone was closely examined. The stone nearly matched record size, but no evidence of man-made marks was found.

Opinion: There was no evidence found to support the stone as being that which was marked in the original survey.

4) The 1/4 Section Corner of Sections 5 and 32, Tps. 12 and 13 S., R. 31 E., W. M., Oregon.

Original record by John B. David, in 1869: "Set stone 17x7x5 for 1/4 sec. corner."

This corner was determined to be lost by Doug Ferguson, RLS, while performing a contract for the Forest Service from 1981-83. Recently, Jack Watson, RLS, while performing a survey for a private land owner, reported finding the original corner stone.

Findings: The alleged corner stone was closely examined. The stone nearly matched record size, but no evidence of man-made marks was found.

Opinion: There was no evidence found to support the stone as being that which was marked in the original survey.

5) The Corner of Tps. 12 and 13 S., Rs. 30 and 31 E., W. M., Oregon.

Original record by John B. David, in 1869: "Set stone 20x10x7 for corner to Townships 12 South Ranges 30 and 31 from which

an Alder, 4 in. diam., bears N. 25° W., 8 lks. dist.

an Alder, 5 in. diam., bears N. 10° E., 8 lks. dist."

This corner was determined to be lost by Doug Ferguson, RLS, while performing a contract for the