



LEGEND

- Found 1½" iron pipe with attached Grant County Surveyor brass cap.
- ⊙ Found 2½" iron pipe with attached brass cap See Survey No. 406.
- ⊙ Set 2½" aluminum pipe with attached 2½" aluminum cap.
- x—x Fence Line
- () Record bearing and distance.
- Found monument, see record map of survey number shown in box.

NARRATIVE

This survey was performed at the request of Darrel Holliday, on behalf of Holliday Family Ranches, Inc.. The purpose of this survey was to establish the N1/4 corner of Section 2 and flag the west line of the E1/2 of Section 2.

This survey was performed using static GPS receivers and Electronic Total Station. The bearings for this survey are based on the GPS survey. The GPS survey was made in NAD 83 State Plane Coordinates, Oregon North Zone. The State Plane Coordinate bearings were rotated clockwise 01 10'45" to true north near the N1/4 corner of Section 2, T14S, R32E. All Bearings are relative to this local north meridian. Grid distances from the GPS survey were multiplied by the combined scale factor of 1.000227589 to compute the ground distances shown on this plat.

A search was made of the available records pertaining to this survey. Field measurements were made to locate existing monuments and provide search areas. The original stone monuments were searched for along the township line. The search areas were disturbed by logging, roads, and fencing activities. The township line is run along the latitudinal curve. The position of the NW corner of Section 1 was established by single proportion between the S1/4 corner of Section 31 and the SE corner of Section 34 and on the latitudinal curve. The N1/4 corner of Section 1 was established on the township line and at the midpoint between the NE and NW corners of Section 2.

RECEIVED AND
FILED

DEC. 7, 2001

OFFICE OF CLERK & SURVEYOR
Robert L. Barger
Attest: *[Signature]*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
SEPT 19, 1995
JACK L. WATSON
2734

Renewal Date 6/30/2002



CORNERSTONE SURVEYING, Inc.

233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY
SITUATED IN SECTION 2, T14S, R32E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR: **Holliday Family Ranches**

SURVEYED BY : Jack Watson

Date: November 5, 2001

DRAWN BY : Jack Watson

MAP OF SURVEY NO. 1617