



Scale 1"=500'

BASIS OF BEARINGS

SURVEY NO. 1601

LEGEND

- Found 2 1/2" aluminum pipe with attached aluminum cap of Record.
- ⊙ Found 1 1/2" galv. iron pipe with attached Grant County Surveyor brass cap.
- ⊙ Set 2 1/2"x30" aluminum pipe with attached 2 1/2" alum. cap, See Corner Restoration Records for details.
- Set 5/8"x30" iron pin with attached 2" aluminum cap, see Corner Restoration Records for details.
- 1() GLO record bearing and distance.
- 2() Survey No. 859 record bearing and distance.
- 3() Survey No. 1601 record bearing and distance.
- Found monument, see record map of survey number shown in box.

NARRATIVE

This survey was performed at the request of King Williams on behalf of Clearwater Land Exchange-Oregon. The purpose of this survey was to establish the corners and boundaries of the SE1/4NE1/4 and the E1/2SE1/4 of Section 30, T12S, R31E, W.M.

The original survey was conducted by John B. David under GLO Contract No. 131, dated June 8, 1869. Subsequent surveys include Map of Survey No.'s 859 and 1601 which are recorded in the office of the Grant County Surveyor.

A search was made of the available records pertaining to this survey and for the original corner stones at the E1/4, S1/4 and the W1/4 corners. No original corner evidence was found at these corners, therefore the positions were established by single proportion as shown. The 1/16 corners were set in accordance with the 1973 BLM Manual and the property lines were flagged.

S88°39'24"W 5372.54
 1(N89°54'E 5256.24)
 3(S88°39'24"W 5372.54)
Basis of Bearings

RECEIVED AND FILED
 JAN. 25, 2002
 OFFICE OF COUNTY SURVEYOR
Robert A. Baird
 Attest: *Michael C. Spang*

REGISTERED PROFESSIONAL LAND SURVEYOR
Jack L. Watson
 OREGON
 SEPT 19, 1988
 JACK L. WATSON
 2734
 Renewal Date 6/30/2002

CORNERSTONE SURVEYING, Inc.
 233 S. Canyon Blvd., John Day, Oregon 97845
 (541) 575-1813

**MAP OF SURVEY
 SUBDIVISION OF SECTION 30
 T12S, R31E, W.M.**

GRANT COUNTY, OREGON

SURVEYED FOR: **CLEARWATER LAND EXCHANGE-OREGON**

SURVEYED BY: Jack Watson Date: January 17, 2002

DRAWN BY: Jack Watson