



LEGEND

- Found 5/8" iron pin with attached aluminum cap. See State Highway Strip Map 8B-35-24.
- Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC.
- Found 2 1/2" aluminum pipe with attached aluminum cap. See Survey No. 1387.
- x—x Fence Line

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Jack L. Watson
OREGON
SEPT 19, 1995
JACK L. WATSON
2734
Renewal Date 6/30/2002

CORNERSTONE SURVEYING, Inc.
233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY PROPOSED PROPERTY LINE ADJUSTMENT SITUATED IN THE NE1/4 AND SE1/4 OF SECTION 14 AND IN THE SW1/4 OF SECTION 13, T13S, R30E, W.M.	
GRANT COUNTY, OREGON	
SURVEYED FOR:	GEORGE MEREDITH
SURVEYED BY :	Jack Watson
Date:	February 5, 2002
DRAWN BY :	Jack Watson

NARRATIVE

This survey was performed at the request of George Meredith. The purpose of this survey was to monument selected points along an existing fence which represents a boundary agreement between adjoining landowners.

The highway right of way was deeded to the State in Book 96, Page 235, deeds of Grant County and shown on Highway strip map 8B-35-24. Strip map 8B-35-24 indicates that pins were set along the right of way as described in the deeds. I accepted the right of way monuments on the south right of way line to place the highway right of way. Monuments were set along the boundary agreement line which generally follows an existing fence line. For the basis of bearings, GPS observations were taken near the SE corner of Section 12. The GPS survey was made in NAD 83 State Plane Coordinates, Oregon North Zone. The State Plane bearings were rotated clockwise 01°02'14" to true north.

RECEIVED AND
FILED

MAR. 4, 2002
OFFICE OF COUNTY SURVEYOR
Robert D. Smith
Attest: *Marshall A. Spayne*