



Scale 1"=200'

### BASIS OF BEARINGS

Survey No. 1449

### LEGEND

- Found 2½" aluminum pipe with attached 2½" aluminum cap, see Survey No. 1449.
- ⊙ Found 1½" iron pipe with attached Grant County Surveyor brass cap, see Survey No. 1157.
- Set 5/8"x30" iron pin with attached 2" alum. cap marked CORNERSTONE SURVEYING, INC. and the appropriate corner designation, see corner restoration sheet filed separately.
- X—X Fence Line
- ( ) Record bearing and distance.

### NARRATIVE

This survey was performed at the request of Richard Naumann. The purpose of this survey was to establish the S1/16 corner on the east line of Section 24.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the E1/4 corner and SE corner of Section 24. The S1/16 corner was set at the mid-point and on line between these corners. A corner restoration sheet was recorded separately for the S1/16 corner.

RECEIVED AND  
FILED  
July 3, 2002  
OFFICE OF COUNTY SURVEYOR  
Attest: *[Signature]*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*[Signature]*  
OREGON  
SEPT 19, 1995  
JACK L. WATSON  
2734  
Renewal Date 6/30/2004

<b>CORNERSTONE SURVEYING, Inc.</b> 233 S. Canyon Blvd., John Day, Oregon 97845 (541) 575-1813	
MAP OF SURVEY SITUATED IN THE SE1/4 OF SECTION 24 T10S, R27E, W.M.	
GRANT COUNTY, OREGON	
SURVEYED FOR: <b>RICHARD NAUMANN</b>	
SURVEYED BY : Jack Watson	Date: 6/27/2002
DRAWN BY : Jack Watson	

MAP OF SURVEY NO. 1639