



### LEGEND

- ⊙ Set 5/8"X30" iron pin with attached 2" alum. cap, see corner restoration records for details.
- X—X Fence Line
- ( ) Record bearing and distance.

### NARRATIVE

This survey was performed at the request of Richard Naumann. The purpose of this survey was to subdivide Section 33, T10S, R28E, W.M.

The original survey along the township line was conducted by E. Thatcher, U.S. Deputy Surveyor, under Contract No. 325, dated June 4, 1879. The township was subdivided by Aaron York, U.S. Deputy Surveyor, under Contract No. 335, dated August 11, 1879. Martin Louther who worked for Port Blakely Mill Co., in the 1950's, recovered the N1/4, S1/4, and E1/4 corners and the SE corner of Section 33. Howard Taylor, PE, found the S1/4 corner and the E1/4 corner of Section 33 in 1958.

This survey was performed using static GPS receivers and Electronic Total Station. The bearings for this survey are based on the GPS survey. The GPS survey was made in NAD 83 State Plane Coordinates, Oregon North Zone. The State Plane bearings were rotated clockwise 00°46'22" to true north. All Bearings are relative to this local north meridian. Grid distances from the GPS survey were multiplied by the combined scale factor of 1.000205318.

A search was made of the available records pertaining to this survey. Field measurements were made to locate the existing fence line and the original corner monuments shown on this plat. In addition to the corners shown on this plat the S1/4 corner of Section 34 was recovered and tied to this survey. Several GLO topographic calls were also located and the position of the SW corner of the township were all used to verify the corner positions along the township line. The section was subdivided in accordance with the 1973 BLM Manual of Surveying Instructions.

RECEIVED AND  
FILED

OCT 15, 2002

OFFICE OF COUNTY SURVEYOR  
Attest: *[Signature]*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*[Signature]*  
OREGON  
SEPT 19, 1995  
JACK L. WATSON  
2734

Renewal Date 6/30/2004



**CORNERSTONE SURVEYING, Inc.**  
233 S. Canyon Blvd., John Day, Oregon 97845  
(541) 575-1813

**MAP OF SURVEY**  
**Dependant Resurvey and Subdivision of**  
**Section 33, T10S, R28E, W.M.**

GRANT COUNTY, OREGON

SURVEYED FOR: **RICHARD NAUMANN**

SURVEYED BY : Jack Watson

Date: 10/01/2002

DRAWN BY : Jack Watson

MAP OF SURVEY NO. 1646