



### LEGEND

- Found 2½" aluminum pipe with attached 3" alum. cap, See Partition No. 2003-4, unless otherwise shown.
- Set 5/8"x30" iron pin with attached 2" alum. cap marked CORNERSTONE SURVEYING, INC. See corner restoration records for details of corner.
- ⊙ Set 2½" aluminum pipe with attached 3" alum. cap, See corner restoration records for details of corner.
- X—X Fence Line
- ( ) Record bearing and distance.
- Found monument, see record map of survey number shown in box.

### NARRATIVE

This survey was performed at the request of Marilyn Allen. The purpose of this survey was to establish the NE corner of the NW1/4SW1/4 of Section 9, T14S, R30E, W.M..

The original survey was conducted by S.W. Lackland, under GLO Contract No. 357, dated July 2, 1880.

A search was made of the available records pertaining to this survey and for the original corner stones at the S1/4 corner and at the SE corner of Section 9. No original corner evidence was found at these corners. I found evidence of the original corner at the E1/4 corner of Section 16. The SE corner of Section 9 was established by double proportion. The S1/4 corner was established at single proportion and the section was subdivided in the usual manner as shown. Corner restoration sheets are recorded separately which give details of the marks upon the caps and the references to the corner monuments. The bearings are based on Land Partition Plat No. 2003-4.

Found 1½" iron pipe with Grant County Surveyor brass cap.

1/4 cor.  
1154

RECEIVED AND  
FILED

MAY 30, 2003  
OFFICE OF COUNTY SURVEYOR  
Robert D. Hargrett  
Attest: Michael C. Spang



**CORNERSTONE SURVEYING, Inc.**  
233 S. Canyon Blvd., John Day, Oregon 97845  
(541) 575-1813

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Jack L. Watson*  
OREGON  
SEPT 19, 1995  
JACK L. WATSON  
2734  
Renewal Date 6/30/2004

MAP OF SURVEY  
SUBDIVISION OF SECTION 9  
T14S, R30E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR: **Marilyn Allen**

SURVEYED BY: Jack Watson

Date: 05/14/2003

DRAWN BY: Jack Watson

MAP OF SURVEY ND. 1664