



LEGEND

- Found 2 1/2" aluminum pipe with attached 3" alum. cap. See Partition No. 2003-4, unless otherwise shown.
- ⦿ Found 5/8" iron pin with attached 2" alum. cap marked CORNERSTONE SURVEYING, INC.
- Set 5/8"x30" iron pin with attached 2" alum. cap marked CORNERSTONE SURVEYING, INC. See corner restoration records for details of corner.
- X—X Fence Line
- () GLO record bearing and distance.
- 1() Partition No. 2003-4 record bearing and distance.
- 2() Survey No. 1664 record bearing and distance.
- Found monument, see record map of survey number shown in box.

NARRATIVE

This survey was performed at the request of Steve Parsons. The purpose of this survey was to establish the SW corner of the E1/2SW1/4 of Section 9, T14S, R30E, W.M..

A search was made of the available records pertaining to this survey and field measurements were made to locate the monuments shown hereon. The W1/16 corner on the south line of Section 9 was set on line and at the mid-point between the S1/4 corner and the SW corner of Section 9. A corner restoration sheet was recorded separately which gives the details of the marks upon the cap and the references to the corner monument. The bearings are based on Survey No. 1664.

RECEIVED AND
FILED

MAY 30, 2003
OFFICE OF COUNTY SURVEYOR
Grant County, Oregon
Attest: *Michael R. Spang*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
SEPT 19, 1995
JACK L. WATSON
2734

Renewal Date 6/30/2004



CORNERSTONE SURVEYING, Inc.

233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY
SUBDIVISION OF SECTION 9
T14S, R30E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR: **Steve Parsons**

SURVEYED BY: Jack Watson

Date: 05/16/2003

DRAWN BY: Jack Watson

MAP OF SURVEY NO. 1665