



Scale 1"=30'

BASIS OF BEARINGS

SURVEY NO. 1573

LEGEND

- Found 2½" aluminum pipe with attached 2½" aluminum cap, See Survey No. 1107.
- Found 5/8" iron pin with attached red plastic cap, See Survey No. 1573.
- Found 1/2" iron pin with attached yellow plastic cap, See Survey No. 365.
- Set 5/8"x30" iron pin with attached red plastic cap marked CORNERSTONE SURVEYING, INC.
- () Record bearing and distance.

NARRATIVE

This survey was performed at the request of Pete Mosso. The purpose of this survey was to locate the boundaries of Lots 1, 2 and 3, of Block 10, of the Townsite of Galena.

A search was made of the available records pertaining to this survey and for the monuments of Survey No. 1573, in Block 10. The lines of Lots 1, 2, and 3 were positioned at record bearing and distances from the monuments found on the south boundary of Lot 6, Block 10. The monument at the NE corner of Lot 5, Block 10, which was set by James Hanley in Survey No. 365, was accepted and used to position the side lines of Second Street. The aluminum pipe monument found on the west boundary of Lot 3 was set at the intersection of the west boundary of the townsite and the north line of the SW1/4SW1/4 of Section 12, by Tyler Parsons, as shown on Survey No. 1107.

RECEIVED AND
FILED

JUNE 30, 2003
OFFICE OF COUNTY SURVEYOR
Attest: *Michael C. Sprague*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
SEPT 19, 1995
JACK L. WATSON
2734

Renewal Date 6/30/2004



CORNERSTONE SURVEYING, Inc.

233 S. Canyon Blvd., John Day, Oregon 97845
(541) 575-1813

MAP OF SURVEY
LOTS 1, 2 & 3, BLOCK 10
TOWNSITE OF GALENA
SITUATED IN THE SW1/4 OF SECTION 12
T10S, R32E, W.M.

GRANT COUNTY, OREGON

SURVEYED FOR: **Pete Mosso**

SURVEYED BY : Jack Watson

Date: June 10, 2003

DRAWN BY : Jack Watson

MAP OF SURVEY NO. 1666