

Map of Survey
of the Corner Monumentation and the
Boundary of the Malheur National Forest
in T.18S., R.28E., Section 27, WM.
Grant County, Oregon



Scale 1"=400'

Basis of Bearing

Solar Observation
near the Corner
26/27/34/35

History

1884—Henry W. Cooke, U.S. Deputy Surveyor, surveyed the subdivisions of the township under GLO Contract #494 dated 01/16/1884 and approved 08/02/1884.

1987—Chris T. Palmer, LS 1288, retraced the north line of section 26. See Grant County Survey #968 dated April 6, 1987.

2001—Jack L. Watson, LS 2734, retraced the east line of section 28. See Grant County Survey #1597 dated April 22, 2001.

Narrative

This survey was performed at the request of the Malheur National Forest for the purpose of marking and defining the Forest Service boundary in Section 27, T.18S., R.28E., WM..

In order to perform this survey a closed loop random traverse was employed using a Wild Total Station. Closure was 1:36,000.

The southeast corner of section 27 was set from original bearing trees, the stone was not recovered. The east 1/4 corner was not recovered after a diligent search of the area. Recent logging in the area disturbed many of the stones. The corner was set by this survey. The south 1/4 corner was recovered and set at the original stones position. The southwest corner of section 27 was recovered as per Grant County Survey #1597 and the northeast corner of section 27 was recovered as per Grant County Survey #968.

Legend

- Posted section line.
- Section line surveyed but not posted.
- NFSL National Forest System Lands
- Found 2 1/2" aluminum pipe with attached 2 1/2" aluminum cap of Record.
- Set 2 1/2" aluminum pipe with attached 3" aluminum cap set from survey.
- ⊕ Set 2 1/2" aluminum pipe with attached 3" aluminum cap from original evidence.
- () Record bearing and distance.
- Found monument, see record map of survey number shown in box.

RECEIVED AND
FILEDSENT: 28, 2004
OFFICE OF COUNTY SURVEYOR
Grant County, Oregon
Attest: *[Signature]*

Renewal Date 6/30/2006

Surveyor's Certificate

I, Carl J. Stout, Registered Professional Land Surveyor, in the State of Oregon hereby certify that this map, notes, and records hereon or referenced are a correct representation of a survey performed during the months of July and August 2004 for the U.S. Forest Service in accordance with the Statutes of the State of Oregon.

Carl J. Stout, PLS 2632
U.S. Forest Service
231 Patterson Bridge Road
John Day, Oregon 97845

Reviewed by:

Teresa Raaf
Teresa Raaf, Forest Engineer

9/20/04
Date

I certify that this survey was performed at the request of the Malheur National Forest Supervisor.

Roger W. Williams
Roger W. Williams, Forest Supervisor

9/20/04
Date