

During this survey, the SW corner of Section 14 was found to be monumented by Robert Bagett from the original GLO stone, in 1976, as shown on Grant County map of Survey No. 393 and on the "Corner Restoration" sheet for this corner, also recorded in the Grant County Records.

A comparison is made from the said fence corner at the S1/4 Sec. 14 to the Grant County Surveyors monument at the SW corner of Section 14. Our survey measured 2621.47 and Byars' reported 2615.58 on the original GLO survey.

Glaze set a stone for the W1/6 between Sections 13 & 24 during said 1913 survey. We made a search at the mid-point between the found stone at the S1/4 of Sec. 13 and the marked rock outcropping at the SW cor. Sec. 13. We found no evidence of Glaze's stone, however a N-S & E-W fence corner is 6' east of the said mid-point.

The above found evidence and measurement comparisons confirm the authenticity and location of those corners. Refer to the "ACCEPTANCE OF FOUND EVIDENCE" later in this report.

At this point, we then evaluate the evidence along the east line of Section 14.

Byars original GLO survey notes read in part;

*North On line bet. Secs. 13 & 14*

*3.50 Enter cultivated field – fence E & W (231 ft.)*

*20.00 Enter brush and balm timber*

*34.00 John Day River, 200 lks. Wide, c. W.*

*36.50 Leave field fence c. E&W*

*37.00 Dalles and Canyon City Road-c. E&W, ascent*

*40.00 Set basalt stone 20x10x6 for the 1/4 sec. cor.*

*80.00 Set volcanic stone 16x14x6 for the cor. to secs. 11,12,13 & 14.*

*Land rolling 2<sup>nd</sup> rate north of road; Level first rate south of same. Timber Cottonwood along river. Brush principally Willow and Thorn. No brush or timber north of river.*

Also pertinent to the evaluation of measurements along the east line of Section 14, from Byars' original GLO survey note, in part;

*North On line bet. secs. 11&12*

*40.00 Set Volcanic Stone 18x12x8 for the 1/4 sec. cor.*

*80.00 Set Volcanic Stone 18x12x10 for the cor. to secs. 1,2,11&12.*

The original topo calls made by Byars will be discussed further in this report.

In Glazes subsequent 1914 survey for the Eastern Oregon Land Company, his note read in part;

	<i>Proceed to common cor's sections 35-36-26-25 thence</i>
<i>N 10629.10</i>	<i>est. common cor's sections 23-24-14-13. set stone marked with notches and c.s. (NOTE: This is the same corner re-established by Glaze in his 1913 survey)</i>
	<i>Thence</i>
<i>N 2590.0</i>	<i>crossing of John Day River</i>
<i>N 2640.0</i>	<i>Est common 1/4 sec. cor. 14-13 set iron post brass marked and wooden post 4x4x4 scribed. Set stone marked 1/4 c.s. erected monument of stone.</i>
<i>N 5280.0</i>	<i>Est. common cor's sec. 14-13-11-12 set iron post Brass cap marked and wooden post 4x4x4 scribed set stone marked with notches and c.s. erected monument of stone. Thence</i>
<i>W 2640.0</i>	<i>Est common 1/4 cor. sec. 11-12 set iron post Brass cap marked and wooden post 4x4x4 scribed set stone marked 1/4 c.s. erected monument of stone</i>
	<i>Thence(from the cor. to secs. 14-13-11-12)</i>
<i>N 2640.0</i>	<i>Gov. common cor. Sec's 11-12. set iron post Brass cap and wooden post 4x4x4 scribed. Set stone marked 1/4 c.s. erected monument of stone.</i>

Note that Glaze's 1914 record notes state that he measured 10629.1 from the corner to Secs. 25,26,35&36 to the SW cor. Sec.13, which he had re-established in his 1913 survey. Byars' original GLO survey returned a distance of 10560 between those same corners.