

This would indicate that Glaze had recovered original GLO evidence at the said corner to Secs. 25,26,35&36. There is no apparent reason why he stated that he set the SW corner Sec. 13 during his 1914 survey.

During this survey, we recovered Glazes Brass capped monuments at the 1/4 corner Secs. 13&14, the NE corner of Section 14 and the 1/4 corner Sections 11 & 12.

At the 1/4 Secs. 13&14, we find that Glaze's Brass cap is set against the west edge of a very old N & E fence corner. The pipe is supporting the west side of the corner jack and is the only thing that is keeping it from moving down the steep slope to the west. We also recovered a 19x14x6 stone marked "1/4" on one face and "CS" on the adjacent face. It should be noted that the "1/4" on this stone is nearly identical to the "1/4" found on the original Byars' GLO stone at the S1/4 Sec. 13, mentioned earlier in this report, and on Byar's stones recovered during previous retracements. This stone, along with other stones that comprised the monument of stone at the said Brass cap have eroded down the steep west slope, 13' west of the cap.

We then compare the above record survey notes to our survey measurements as follows;

Between the found Glaze Monument(marked rim) at the SW cor. Sec 13 to the Glaze brass cap at the 1/4 cor. Secs. 13&14

Byars' record North 40.00 chs(2640.00 ft.)
Glaze's 1914 record North 2640.0
This survey N00°01'26"E, 2693.69

Between the found Glaze brass caps at the 1/4 Secs. 13&14 and the corner to Sections 11,12,13&14:

Byars' record North 40.00 chs.(2640.00)
Glazes 1914 record North 2640.0
This Survey N00°05'43"W, 2579.95

Note that Glaze states in his 1914 record survey notes, "*Est. common cor's sec. 14-13-11-12*".

Between the found Glaze brass caps at the corner to Sections 11,12,13&14 and the 1/4 corner Secs. 11&12;

Byars' record North 40.00 chs(2640.00 ft.)
Glaze's 1914 record North 2640.0
This Survey N00°45'57"E, 2687.30

Note that Glaze states in his 1914 record survey notes, "*Gov. common cor. Sec's 11-12*"

Byar's record distances between the 1/4 corner to Secs. 13 & 14 and the 1/4 corner to Secs. 11 & 12 is 5280.0. Note that Glaze's 1914 survey also shows 5280.0. The distance returned between those corners during this survey is 5267.25, a difference of 12.75 ft. This may also indicate that Glaze recovered the original GLO stone at the 1/4 cor. Secs. 13 & 14.

It should be noted, as stated earlier in this report, that the above found evidence and measurement comparisons confirm the authenticity and location of the brass cap monuments as set by Glaze in 1914. Refer to the "ACCEPTANCE OF FOUND EVIDENCE" below.

At the W1/4 corner , the N1/4 corner and the NW corner of Section 14, we found the Brass capped Monuments as set by Glaze during his 1913 survey.