

Continuing with Glaze 1914 Survey:

Thence

North 2590.0, crossing John Day River

The call to the "John Day River" would move the monument at $\frac{1}{4}$ S14/S13 South from 100 to 300 feet, depending on the location of the river when he made the call.

North 2640, Established common $\frac{1}{4}$ Sec. Cor 14-13

Set iron post, Brass cap marked and wooden post 4x4x4.0 scribed, set stone marked $\frac{1}{4}$ CS erected mount of stone.

North 5280.0 Established common Cor's Sec's 14-13-11-12, set iron Post Brass Cap, Marked an wooden post 4x4x4.0 scribed, set stone marked with notches and erected monument of stone

Thence (from above cor 14-13-11-12)

West 2640.0 Established Common $\frac{1}{4}$ Sec. Cor. 11-14, set iron post Brass cap marked & wooden post 4x4x4.0 scribed, set stone marked $\frac{1}{4}$ CS, erected monument of stone.

Thence (from above cor 14-13-11-12)

North 2640, Gov. Cor. Common $\frac{1}{4}$ Cor Secs 11-12, set iron post brass cap marked and wooden post scribed, set stone marked $\frac{1}{4}$ CS, erected monument of stone.

Thence (continuing north)

North 5280, Gov. Cor. Common Cor. Secs 11-12-2-1 set iton post brass cap marked and post 4x4x4.0 scribed. Set stone marked with notches and CS, erected monument of stone.

North 2656.0, Gov common. Cor $\frac{1}{4}$ Secs 2-1 set iron post Brass cap marked and wooden Post 4x4x4.0 scribed set stone marked $\frac{1}{4}$ CS, erected monument of stone.

Return to secs cors 2-1-11-12

East 2640.0 Established common $\frac{1}{4}$ cor 1-12 set iron post Brass cap marked and wooden post 4x4x4.0 scribed, set stone marked $\frac{1}{4}$ CS erected monument of stone

Return to Secs cor 10-11-15-14

There is no record of this corner being re-established by Glaze. We therefore assume that Glaze recovered original evidence here.

West 2640.0 Gov Common cor $\frac{1}{4}$ (10/15) set iron post Brass cap marked and wooden Pos 4x4x4.0 scribed erected monumeni of stone

Return to Secs cor 10-11-15-14

North 2640.0 Common Gov $\frac{1}{4}$ Cors sec. 10-11. set iron post Brass cap marked and Wooden post 4x4x4.0 scribed erected monument of stone